



INTERNATIONAL
2011 PRODUCT CATALOGUE

E9000.0047F

A HISTORY OF INNOVATION AND COMMITMENT



Understanding and responding to customer requirements has always been important to the **Bunn-O-Matic Corporation (BUNN®)**. Over 160 years ago, Jacob Bunn opened his grocery store in Springfield, Illinois, USA, and a young Abe Lincoln was one of the first customers. Five generations later, BUNN has become a global partner you can count on for profitable, reliable beverage equipment and outstanding post-purchase support wherever customers are served.

Since 1957, **BUNN** has been at the forefront of beverage equipment innovation: inventing the flat-bottom paper filter for commercial use, the pour-over coffee brewer, and the first commercial iced tea brewer that uses fresh leaves versus instant mix.

As customers entered the digital age, **BUNN** also embraced sophisticated new technology to help you serve excellent coffee and beverages and build profits. The company currently manufactures a complete line of dispensed beverage equipment including coffee brewers and grinders; liquid coffee dispensers, iced tea brewers; hot chocolate, granita, and juice machines; precise temperature water systems; water quality systems and paper filters.

In 2010, the company launched a new single cup brewer, the trifecta™. This product illustrates an ongoing commitment to delivering the highest possible quality beverage in each cup.

BUNN assures high quality products by adhering to strict guidelines at production plants. This dedication to quality resulted in an upgrade in the manufacturing facilities' quality management registration through ISO 9001:2000.

With thousands of loyal commercial and retail customers, the BUNN brand is synonymous with honesty, integrity, courtesy and quality, all of which work together to uphold the company's brand promise, **A Partner You Can Count On™**.

The global headquarters are located in Springfield, Illinois, USA, where the company strives for total customer satisfaction through superior equipment and unmatched customer service with support from plants and warehouses in five North American locations, as well as warehouses or offices in Mexico, Germany, China and the United Kingdom.

For more information, please visit www.bunn.com or call +1-217-529-6601. Find us on Facebook at www.facebook.com/BUNN or follow us on Twitter at www.twitter.com/BUNN.

NEW ITEMS



PAGE..5

Experience air infusion brewing with bubble action from the trifacta.

PAGE..40

The G9WD-HD delivers unparalleled grind weight accuracy for the right amount of coffee every time.



The G2 trifacta grinder yields an expanded range of precise grinds.

PAGE..45

We are A Partner You Can Count On™ in the journey to a perfect cup.


BUNN
WWW.BUNN.COM



TABLE OF CONTENTS

Single Serve Brewers.....	3
Air Infusion Brewer.....	5
Pourover Brewers.....	6
Automatic Decanter Brewers and Urns.....	10
Thermal Coffee Brewers	14
Satellite Coffee Brewers	24
Coffee Grinders	39
Liquid Coffee High Volume Systems	46
Iced Tea and Coffee Brewers.....	48
Hot Beverage Systems.....	52
Cold Beverage Systems	57
Frozen Beverage Systems	61
Precise Temperature Water Dispensers	63
Related Products	
Servers	21,23,28-29,34,37
Iced Tea/Coffee Dispensers.....	50-51
Water Quality Filter Systems	66
Paper Filters.....	67
Decanters and Warmers.....	68-69
Universal Airpot Racks.....	70
Stock Funnels	71
Special Purpose Funnels.....	72
Drip Trays	73-74

CATALOG ICON LEGEND



AGENCY SYMBOLS

NSF International	Electrical Testing Labs Sanitation	GOST-R Russia Safety, Sanitation, EMC
Electrical Testing Labs Safety	KETI South Korea Safety	KSA Kingdom of Saudi Arabia
CE Listed	Argentina Safety	China Compulsory Certification
UL Listed		

ELECTRICAL REQUIREMENTS

Please refer to installation manuals for complete specifications and instructions. 230 Volt 50/60Hz models require 2 wires plus ground service rated 220-240V, single phase. 220 Volt 60Hz models require 2 wires plus ground service rated 220-240V, single phase. 100 or 200 Volt 50Hz or 50/60Hz models require 2 wires with ground, single phase. Multi-Phase models: 3-Phase to phase = 400V (will work on any voltage rated 380-415). Phase to neutral = 230V; 4 wire plus ground, 50/60Hz, 3 active heaters.; 1-Phase - Voltage = 230, 2 wire plus ground, 50/60Hz, 2 active heaters.

TRADEMARKS

392; AutoPOD, AXIOM, BrewLOGIC, BrewMETER, Brew Better Not Bitter; BrewWISE, BrewWIZARD, BUNN Espresso, BUNN Family Gourmet, BUNN Gourmet, BUNN Pour-O-Matic, BUNN, BUNN with the stylized red line, BUNN Ink, Bunn-O-Matic, Bunn-O-Matic, BUNNserve, BUNNSERVE with the stylized wrench design, Cool Froth, DBC, Dr. Brew stylized Dr. design, Dual, Easy Pour, EasyClear, EasyGard, FlavorGard, Gourmet Ice, Gourmet Juice, High Intensity, iMIX, Infusion Series, Intellisteam, My Café, PowerLogic, Quality Beverage Equipment Worldwide, Safety-Fresh, savemycoffee.com, Scale-Pro, Silver Series, Single, Smart Funnel, Smart Hopper, SmartWAVE, Soft Heat, SplashGard, The Mark of Quality in Beverage Equipment Worldwide, ThermoFresh, A Partner You Can Count On, Air Brew, Air Infusion, Beverage Bar Creator, Beverage Profit Calculator, Brew better, not bitter., BUNNsource, Coffee At Its Best, Cyclonic Heating System, Digital Brewer Control, Nothing Brews Like a BUNN, Pouring Profits, Respect Earth, Respect Earth with the stylized leaf and coffee cherry design, Signature Series, Tea At Its Best, Phase Brew, The Horizontal Red Line, Titan, triecta, Ultra, Velocity Brew are either trademarks or registered trademarks of Bunn-O-Matic Corporation.

BUNN SUSTAINABILITY FEATURES



RoHS Compliant: In keeping with our Sustainability Mission, BUNN electronics design can be made with NO hazardous substances and part assemblies are recyclable wherever possible.

Lead-free Solder is specified in the production of all electronic control boards.

Energy Saver Modes will lower power usage by disabling warmers and tank heater during periods of inactivity.

LED Lighting is being specified where possible for product displays. LED lights use considerable less energy than fluorescent or incandescent lighting and have a longer life.

Corrugated, Biodegradable Materials are gradually replacing Styrofoam packing.

HFC-free Foam Insulation (no hydro fluorocarbons) is now used exclusively to insulate Soft Heat® servers and the cabinets of liquid coffee and cold beverage dispensers.

GENERAL TERMS

Bypass (and variable bypass): A function, like dilution, that reduces strength of a concentrate but it is intended for hot beverages. Generally, hot water is blended with coffee concentrate. Variable bypass allows different bypass rates for various brew volumes (small, medium and large) within a recipe.

Cold brew lock-out: A programming feature that prevents brewing when actual water temperature is below the Ready temperature.

Dilution: A function used to reduce strength of a concentrate for cold beverages. Generally ambient tap water is blended with tea or coffee concentrate.

Drip Time: Setting of time from the end of the spray head flow until the funnel flow stops (also applies to funnel lock).

Easy Pulse: This is a simplified version of Pulse Brew. It is programmed by selecting the time period of brew water dispense. Easy Pulse allows the operator to input a set time for which the brewer software will determine a pulse sequence.

Extraction: Water-soluble materials dissolve and move out of the coffee grounds and into the water. Part of the brewing process that includes Wetting and Hydrolysis.

Funnel lock: A safety feature to prevent funnel removal during drip time.

Hydrolysis: A chemical reaction where the materials created during extraction break down further into water-soluble proteins and sugars. Part of the brewing process that includes Wetting and Extraction.

Pre-Infusion: A minor adjustment to a brew cycle when an initial volume is dispensed, followed by a pause to allow for saturation of the material, then the remainder of the brew cycle progresses. This is also described as a "pre-soak."

Pulse Brew: A method used to increase the water contact time during a brew cycle. Pulse Brew can be programmed manually, by set time or through BrewMETER adjustments. This method is very useful for smaller volumes.

Satellite Brewer: A system that includes a mother brewing system that remains in one location (e.g., kitchen) and dispenses into portable, or removable, servers for remote service.

Wetting: Grounds begin to absorb hot water from the sprayhead and release gasses from the coffee. Part of the brewing process that includes Extraction and Hydrolysis.

EXCLUSIVE BUNN PROGRAMMING AND DESIGN FEATURES

BrewLOGIC®: A programming feature that compensates for flow rate variations to maintain consistent dispense levels when water quality is a consideration.

BrewMETER®: A programming feature that simplifies Pulse Brew and allows extraction manipulation with the touch of a button.

BrewWISE®: A programming feature with Radio Frequency Identification (RFID) communications between grinder, funnel and brewer for custom warmer and recipe management without error. Works in conjunction with SMART Hopper, SMART Funnel, and a Recipe Writer/Card.

BrewWISE® Recipe Writer/Card: Creates recipe cards or dedicated funnels for coffees, dramatically reducing equipment installation and calibration time. A box connects to a Windows® PC with a standard serial port and uses BUNN software to transfer information to the cards or a SMART Funnel, then to-and-from the BUNN BrewWISE brewer and grinder. Ensures consistently high quality coffee flavour at every location and can also make cards for advertising messages onto the brewer's display.

BrewWIZARD® – A programming feature that provides quick access to the most utilized setup parameters including a lock-out feature to prevent brewing when actual water temperature is below the Ready temperature. Features include: brew lock-out, brew ounces, enable ads, enter service number, and BrewMETER®.

BUNNLink®: An automated monitoring and communication system that detects pending service problems and forwards alerts for service.

DBC®: Digital Brewer Control. BUNN was among the first in the dispensed beverage industry to introduce advanced beverage technology to the industry with Digital Brewer Control systems that allow users to precisely and consistently meet specific flavour profiles while also reducing training and labour costs.

Easy Pour®: An exclusive design used in decanters to assure convenient serving with a drip-proof, fast pouring lip from front or either side.

FlavorGard®: Technology that continuously monitors extract-to-water ratio and assures flavour consistency.

High Intensity®: Technology that mixes high viscosity concentrates thoroughly, consistently, and accurately to the required brix setting. The consistent results ensure the best quality beverage in the cup and contribute to maximum profits in the beverage program.

Infusion Series®: A product line of coffee/tea brewers that allow different brewing profiles from the same machine/footprint, saving valuable counter space.

RPM Feedback: Technology on auger motors in BUNN specialty drink systems that monitor the auger revolutions per minute (RPM) and controls powder dosing for each beverage, eliminating product waste and ensuring consistency cup-to-cup.

Safety-Fresh®: A brew-through lid with a vapor seal to maintain freshness and a spill prevention design.

Smart Funnel®: A funnel designed with a microchip that can receive information from an enabled grinder and transfer that information to an enabled brewer, managing the grinding and brewing process from start to finish. A SMART Funnel can be programmed to accept dedicated recipe information, reducing labour costs and minimizing brewing errors. Used in conjunction with BrewWISE technology.

Smart Hopper®: A hopper designed with a microchip that communicates the type of coffee contained in the hopper to an enabled grinder, managing the grinding and brewing process from start to finish. Used in conjunction with BrewWISE technology.

SmartWAVE®: Turbulence is an important element in brewing

perfect coffee. SmartWAVE is a BUNN exclusive product design that uses technology to increase turbulence in the brew funnel, providing more contact between water and coffee and uniformity of extraction.

Soft Heat®: A docking server system with technology that thermostatically controls and automatically shuts off heat in the docking system once the preset temperature is reached and additionally monitors server volume. This is more beneficial than traditional warmer plates that heat continuously.

SplashGard®: An exclusive design with a shield next to the funnel handle that deflects hot liquids away from the user's hand.

ThermoFresh®: BUNN offers a full line of vacuum-insulated servers and brewers that brew directly into these servers that keep coffee at optimal flavour for hours and save on energy consumption and by not requiring warming plates.

ABBREVIATION KEY FOR MODEL DESCRIPTIONS

1L/2U – 1 Lower, 2 Upper Warmers	FLSH – Flashing Lamp	PF – Plastic Funnel
2W1PH – 2 Wire 1 Phase	FR – Front	PK – Pack
3L – 3 Lower Warmers	FNL KIT – Funnel Kit	PKG – Package, Packaging
3W3PH – 3 Wire 3 Phase	FLK – Funnel Locks	POSN – Position
6HL – 6 Hole	FMD – Fresh mix dispenser	PO – Pourover Feature
7HL – 7 Hole	G – Gallon	PR – Pourover
"A" and "P" – used in conjunction with a product name to indicate "Automatic" (water line required) or "Pourover" (no water line necessary, plug-in operation).	GF – Gourmet Funnel	PWR CRD – Power Cord
ADP – Adapter	GRY – Gray	QTEA FNL – Quick Tea Funnel
AFI – Auto Fill Installed	GP – Group	QK CONN – Quick Connect
APS – Airpot Server	HDL – Handle	RSD – Raised
ASSY – Assembly	HIALT – High Altitude	RDY LT – Ready Light
AUX – Auxiliary	HILM – High Line	REM – Removable
BASE, BA – Base	HL – Hole	RSVR – Reservoir
BLK – Black Finish	HPR – Hopper	RT – Right
BRKT – Bracket	HWV – Hot Water Valve	SRVR – Server
BRW – BrewWise Recipe Writer	INTFC – Interface	SB – Shipboard
BW – BrewWise	LAF – Liquid autofill	SIDEHNDL – Side Handle
CS – Case	LTD SW – Lighted Switch	SINGL – Single
CL – Cluster	L – Liter	SMT FNL – Smart Funnel
CWV – Cold Water Valve	LEVR – Lever Action	SMK FNL – Smoked Funnel
CONN – Connect	LF – Lower Faucet	SH – Soft Heat
CTNR – Container	LP – Low profile	SPHD – Sprayhead
CONC – Concentrate	H&C – Hot and cold	SF – Stainless Steel Funnel
CVRSN – Conversion	MB – MultiBrewWISE	SS – Self Serve
DGTL – Digital	MECH – Mechanical	SST – Stainless Steel Finish
DBC – Digital Brewer Control	MHG – Multi hopper grinder	SWTNR – Sweetener
DT – Drip Tray	MNL – Manual	TC – Thermal Carafe
DV – Dual voltage	MP – Multi Phase	TS – Thermal Server
EXP – Export	MTG – Mounting	TF – Thermo Fresh
FF – Fast Flow	NKL – Nickel	TRK – Trunk
FTG – Fitting	NO LITE – No Fresh Light	WB – Wall Bracket
	NO BASE – Without Base	WD – Weight driven
	NODTRAY – No Drip Tray	WRMR – Warmer
	NO WRMR – No Warmer	WHT – White
	ORN – Orange	WHT/SST – White/Stainless
	PAF – Powder autofill	
	PC – Portion Control	

My Café® AutoPOD® Pod Brewer



AP AutoPOD

Commercial-grade, single-cup system with the convenience of automatic pod disposal

- Eliminates waste by brewing one fresh cup at a time from a wide variety of coffee and tea pods.
- Automatically disposes of spent pods after each brew.
- Removable pod bin holds up to 25 pods.
- Pod bin and drip tray can be modified for under-counter disposal of pods.
- Works with most coffee and tea pods.
- Sprayhead design allows for proper extraction of all flavouring materials and aromatics.
- Brews up to 473 mL of coffee or tea in less than a minute.
- Digital display in English/Spanish for easy programming, operation and control.
- Control extraction utilizing pulse brew technology with BrewMETER®.
- Push and hold hot water button provides up to 296 mL of hot water for cocoa and soups.
- Integrated cup booster allows for 12.7cm or 20.3cm cup clearance.
- Energy Saver Mode.

RELATED PRODUCTS


Inlet Hose Assembly
Product No.: 32865.0002



Rack Assembly



Brew Station and I Rack Assembly



Product #	Model	Weight	Volts	Amps	Watts	Hertz	Cord	Agencies
40300.0003	AP AutoPOD	13.6 kg	230	6	1380	50/60	EURO	CE
39501.0001	Brew Station (with Standard Header)	11.8 kg						
39502.0001	Rack Assembly	3.6 kg						


Plumbing: 138-621 kPa. Machine supplied with strainer and 1/4" male flare fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

My Café[®] Automatic and Pourover Pod Brewers



MCA Automatic


- Pod drawer works with most tea and coffee pods, from 45 to 61 mm.
- Fast brew coffee in about 30 seconds; brew tea in less than one minute.
- Sprayhead allows extraction of all coffee flavouring materials and aromatics.
- Tea button features pulse brew technology to provide steeping action.
- Brew 118 - 355 mL of coffee or tea to preferred strength by adjusting the portion/volume control.
- Easy to use and maintain with a removable water reservoir; a drawer-style pod holder and dishwasher safe components.
- Energy Saver Mode. 
- Automatic model is connected to waterline, eliminating manual reservoir refills.
- Includes two pod holders.












RELATED PRODUCTS

Inlet Hose Assembly
Product No.: 32865.0002



MCP Pourover



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agencies
35400.0014	MCPA, Pourover	9.75 lbs. (4.4 kg.)	230	6	1330	50/60	1	UK	  
35400.0015			EURO						
35400.0018			220/230					KOREA	  
35400.0016	MCAA, Automatic	11.35 lbs. (5.1 kg.)	230					UK	  
35400.0017			EURO						
35400.0019			220/230					KOREA	 
Plumbing: 138-621 kPa. Machine supplied with strainer and 1/4" male flare fitting. All plumbed models that are CE listed feature backflow prevention.									

trifecta™ Single Cup Air Infusion™ Brewer



trifecta

Tech-enabled, barista-crafted single cup brewer that heightens the quality of coffee and tea

Every coffee has a voice. With the trifecta, the barista creates an experience which unlocks the nuances of that coffee. Using an air infusion single cup process, the trifecta brews so that each coffee's unique voice resonates.

trifecta BREWING PHASES

1. **Wetting:** The saturation of the coffee grounds can be controlled to get the percentage of water and pause appropriate for that coffee.
2. **Extraction:** Air is injected into a pressurized chamber so that the grounds are agitated -- the result: uniformity of extraction and a complex beverage that will be enjoyed by a coffee lover.
3. **Hydrolysis:** Air presses the beverage through a metal screen that filters out coffee grounds while preserving coffee oils and aromatics for a deep-bodied, unique coffee experience.



See *trifecta grinder* on page 45.

Visit www.trifectaexperience.com for more information.

Scan this code with your smartphone to view more information on the trifecta. QR code reader required.



NOTE: Catalog icon legend can be found on page 1.



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agencies
41200.0001	trifecta	18.9 kg	230	5.8	1330	50/60	1	Yes	CE
41200.0002	trifecta		100	14	1400				

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Coffee Brewers with 2 Warmers



- Space saving 21.1 cm wide.
- Pour-over brewer requires no plumbing – completely portable.
- Consistently brews perfect coffee in about 3 minutes at 92°C.
- All stainless steel tank construction.
- Two separately controlled warmers.
- Includes paper filter pack and pour-in pitcher .
- Ready light.

RELATED PRODUCTS

Regular Filter Pack
Product No.: 20115.0000




Warmer stands
See page 69 for details



Decanters sold separately
See page 68 for details



392



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
37800.0106	392	10.9 kg	100	14.3	1425	60	I	NEMA	
37800.0107	392		220-240	9.6-10.5	2300	50/60		UK	CE KSA
37800.0108								EURO	CE PC
37800.0110								No	CE CCC

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Coffee Brewers with I Warmer



VP17-I

- Under 45.2 cm tall.
- Brews up to 22 litres of coffee per hour.
- Pour-over brewer requires no plumbing – completely portable.

RELATED PRODUCTS

Regular Filter Pack
Product No.: 20115.0000





Power Cord
Product No.: 27728.0005

Warmer stands
See page 69 for details



Decanters sold separately
See page 68 for details



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
13300.0024	VP17A-I, black, plastic funnel	9.6 kg	220-230	9-9.5	2000-2160	50/60	I	No	CE KSA

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Coffee Brewers with 2 Warmers



VP17-2

An integral part of any office coffee service program

- Brews 17.4 to 22 litres of coffee per hour.
- Requires no plumbing – completely portable.
- Just pour cold water in top and coffee brews immediately.
- Two separately controlled warmers.

RELATED PRODUCTS

Regular Filter Pack
Product No.: 20115.0000







Power Cord
Product No.: 27728.0005

Warmer stands
See page 69 for details



Decanters sold separately
See page 68 for details



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency	
I3300.0015	VP17A-2	11.3 kg	230	10.0	2260	50/60	I	No	CE  KSA	
I3300.0038	VP17A-2	10.9 kg	220	9.5	2100	60				
I3300.0041	VP17A-2, Master ON/OFF		220-230	9.5-10	2100-2260	50/60		UK	CE  KSA	
I3300.0042	VP17A-2, Gourmet funnel							Yes		

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Coffee Brewers with 3 Warmers



VP17-3

An integral part of any office coffee service program

- Brews 13.6 to 28.4 litres of coffee per hour.
- Requires no plumbing – completely portable.
- Just pour cold water in top and coffee brews immediately.
- Three separately controlled warmers.

RELATED PRODUCTS

Regular Filter Pack
Product No.: 20115.0000





Warmer stands
See page 69 for details




Decanters sold separately
See page 68 for details



VP17-3



3 Lower Warmers



2 Upper Warmers


Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
I3300.0020	VP17A-3, 3 lower warmers	14.1 kg	220-230	15-15.5	3290-3560	50/60	1	No	CE
I3300.0028	VP17B-3, 1 lower/2 upper warmers	12.7 kg	100	15	1495	50		Yes	
I3300.0037	VP17A-3, 3 lower warmers SST	14.1 kg	220-230	15-15.5	3290-3560	50/60		No	CE KSA
I3300.0049	VP17A-3, 3 lower warmers SST, Korea		220	15	3290-3560	60			CE

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.


AXIOM® Coffee Brewers



AXIOM



AXIOM - 3 lower



AXIOM - 2 upper, 1 lower

Medium volume brewing solution featuring simple operation, precise extraction control

- Brews up to 28 litres of coffee per hour.
- Large 5.9 litres tank provides back-to-back brewing capacity.
- Digital display in English/Spanish for easier programming and control. Display capable of showing English or Metric measurements.
- BrewWIZARD® technology incorporates simplified programming with a LCD display.
- BrewLOGIC® technology calculates flow rate and adjusts brew time to maintain consistent pot levels.
- Digital temperature control for accuracy
- Adjusts automatically to varying water pressure.
- Pot level, cold brew lock-out and tank temperature set easily from advanced touch pad on front of machine.
- Electronic diagnostics and built in tank drain make service easier.
- Coffee extraction controlled with pre-infusion or pulse brew and digital temperature control.
- Automatic warmer shut-off.
- Energy Saver Mode.

RELATED PRODUCTS

Regular Filter Pack

Product No.: 20115.0000



ED-17-TL

Product No.: 30201.1001

Product No.: 30200.1000



Inlet Hose Assembly

Product No.: 32865.0001

Decanters sold separately
See page 68 for details.



AXIOM

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
38700.0004	AXIOM 1 lower warmer; 2 upper warmers	13.6 kg	230	9	2100	50/60	1	Yes	
38700.0005	AXIOM 3 lower warmers	14.1 kg							
38700.0006	AXIOM 1 upper warmer; 2 lower warmers	13.6 kg	200	19	3800				
38700.0007	AXIOM 3 lower warmers	14.1 kg							
38700.0033	AXIOM-3, 1 upper warmer; 2 lower warmers	13.6 kg	220 - 230	15.4 -16	3400 -3600				
38700.0051	AXIOM 1 upper warmer; 2 lower warmers, 1/2 batch, SST funnel	13.6 kg	200	19	3800				
38700.0055	AXIOM 1 upper warmer; 2 lower warmers, 1/2 batch, SST funnel	14.1 kg	100	15	1500				

Plumbing: 138-621 kPa. Machines supplied with 1/4" male flare fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Coffee Brewers with Upper/Lower Warmers



CWTF

- Brews up to 28.4 litres of coffee per hour.
- Hot water faucet and pourover feature on most models.

RELATED PRODUCTS

Regular Filter Pack
Product No.: 20115.0000



ED-17-TL
Product No.: 30201.1001
Product No.: 30200.1000




Inlet Hose Assembly
Product No.: 32865.0001




Decanters sold separately
See page 68 for details




CWTF




















CWTF Lower



CWTF Upper



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
I2950.0277	CWTF35A, 1 lower/2 upper warmers, plastic funnel	13.6 kg	220-230	15	3300	50/60	I	No	  
I2950.0317	CWTF4, 1 lower/2 upper warmers, plastic funnel		230	10.4	2400				   
I2950.0325	CWTF35A, 3 lower warmers, plastic funnel	17.3 kg		15.6	3580	  			
I2950.0413	CWTF35A, 1 lower/2 upper warmers	14.5 kg	220	15	3300	60			  
I2950.0414	CWTF4, 1L/2U warmers, plastic funnel	14.1 kg		10	2200				  
I2950.0436	CWTA, 1 lower/2 upper warmers, no faucet	13.6 kg	230	10.4	2400	50/60			

Plumbing: 138-621 kPa. Machines supplied with 1/4" male flare fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Coffee Urns



- Brews up to 43.2 litres of coffee per hour.
- Automatic drip brewing of delicious coffee every time.
- Large water tank - holds 37.9 litres.
- Draw off hot water during brewing cycle without affecting delivery of coffee.
- Can brew full or half batches.
- Top mounted components for ease of service.

RELATED PRODUCTS

Urn Filter Pack

Product No.: 20109.0000



EQHP-10

Product No.: 39000.0004



EQHP-25

Product No.: 39000.0005



EQHP-25L

Product No.: 39000.0002



Drip Tray

Product No.: 06465.0000

Inlet Hose Assembly


Product No.: 32865.0002

Decanters sold separately
See page 68 for details



12

SRU



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
06325.0013	SRUA	37.2 kg	230	16	3650	50	I	No	CE
06325.0016	SRUA with shroud			24	5500				

Plumbing: 138-621 kPa. Machine supplied with 3/8" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Coffee Urns



U3

- Brews 61.7 to 71.2 litres of coffee per hour.
- Automatic drip brewing of delicious coffee every time.
- Large water tank - holds 75.7 litres.
- Draw off hot water during brewing cycle without affecting delivery of coffee.
- Can brew full or half batches.
- Top mounted components for ease of service.

RELATED PRODUCTS

Urn Filter Pack

Product No.: 20109.0000



EQHP-10

Product No.: 39000.0004



EQHP-10L

Product No.: 39000.0001



EQHP-25

Product No.: 39000.0005



EQHP-25L

Product No.: 39000.0002

Drip Tray


Product No.: 07284.0000





Inlet Hose Assembly

Product No.: 32865.0002

Decanters sold separately
See page 68 for details



U3 WITH WATER BYPASS



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
20500.0010	U3A	37.2 kg	230	26.5	6100	50	I	No	CE
20500.0016	U3A with shroud								

Plumbing: 138-621 kPa. Machine supplied with 3/8" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Infusion Coffee Brewers



ICB

- Large 11.36 litre tank provides back-to-back brewing capacity.
- Three brew buttons allow for 3 separate brewing profiles. Two programmable batch switches allow full and half batch brewing.
- Brews into 2.5 to 3.8 litre airpots and 3.8 and 5.7 litre baseless ThermoFresh® servers.
- BrewWISE® intelligence with pre-infusion, pulse brew and by-pass for maximum flavour extraction.
- Energy Saver Mode.
- Digital display in English/Spanish/Katakana for easier programming and control. Advertising messages and machine status also displayed.
- Display capable of showing English or Metric measurements.

ICB TWIN

- Large 21.2 litre tank allows brewing up to 71.5 litres per hour of perfect coffee.

RELATED PRODUCTS

Single/Dual Filter Pack
Product No.: 20138.0000



EQHP-10
Product No.: 39000.0004





EQHP-10L
Product No.: 39000.0001

Inlet Hose Assembly
Product No.: 32865.0002



Servers and stands sold separately
See pages 21, 28-29 for details



ICB TWIN

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
36600.0001	ICBA	21.5 kg	230	13	3000	50/60	1	No	CE
36600.0002	ICBB		200	18	3600				
37600.0008	ICBA-Twin	21.5 kg	230	26	6000	50/60		No	CE



Plumbing: 138-621 kPa. Machine supplied with 3/4" hose thread adapter and fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Infusion Coffee Brewers



ICB-Tall

- Large 11.36 litre tank provides back-to-back brewing capacity.
- 87.4cm trunk height accommodates both 3.8 litre and 5.7 litre TF servers with base.
- Three brew buttons allow for 3 separate brewing profiles. Two programmable batch switches allow full and half batch brewing.
- Brews into 2.5 to 3.8 litre airpots and 3.8 and 5.7 litre baseless ThermoFresh® servers.
- BrewWISE® intelligence with pre-infusion, pulse brew and by-pass for maximum flavour extraction. 
- Energy Saver Mode. 
- Digital display in English/Spanish/Katakana for easier programming and control. Advertising messages and machine status also displayed.
- Display capable of showing English or Metric measurements.

RELATED PRODUCTS

Single/Dual Filter Pack
Product No.: 20138.0000





EQHP-10
Product No.: 39000.0004



EQHP-10L
Product No.: 39000.0001

Inlet Hose Assembly
Product No.: 32865.0002

Servers and stands sold separately
See pages 21, 28-29 for details



NOTE: Catalog icon legend can be found on page 1.


Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
36600.0006	ICBA-Tall	23.1 kg	230	14	3200	50/60	1	Yes	CE 

Plumbing: 138-621 kPa. Machine supplied with 3/4" hose thread adapter and fitting. All plumbed models that are CE listed feature backflow prevention.


SmartWAVE® Low Profile Brewers





WAVE-S



legs extended to accommodate 2.5L push-button airpot



Low profile brewer featuring SmartWAVE technology, simple operation, and flexible server options

- Brews up to 14.8 litres of coffee per hour.
- Brew into 1.9L thermal carafe utilizing the slide-out booster tray.
- Adjustable legs to accommodate up to 3.0L* lever action, 2.5L push button BUNN airpots, and 2.5L thermal server. (*Due to brewer's capacity, it's recommended you not brew larger than 2.5 litres of finished product.)
- Low profile brewer ideal for counter top applications, adjustable height dimensions from 43cm to 47.5cm, fixed 22.2cm width and 43.8cm depth.
- SmartWAVE® technology increases turbulence in the brew funnel. 
- Ensures coffee brew quality with cold brew lock out capability.
- Hot water faucet.
- Energy Saver Mode. 
- Analog switches accompanied by red/green LED for programming.
- LED provide brewer status (ready, heating, brewing).
- Choice of three pulse brew routines to adjust your flavour profile

RELATED PRODUCTS

Regula Filter Pack

Product No.: 20115.0000



EQ-17-TL

Product No.: 30200.1000



ED-17-TL

Product No.: 30201.1001



**Servers sold separately
See pages 21 and 23 for details.**

Brewer Position	BUNN Part #	Description	Brewer Height
Utilizing thermal carafe tray	36029.0001	1.9L deluxe thermal carafe	42.93cm
Utilizing thermal carafe tray	40163.0000	1.9L economy thermal carafe	42.93cm
LP feature (lowest)	39430.0000	1.9L thermal pitcher	42.93cm
LP feature (lowest)	32125.0000	2.5L lever-action airpot	42.93cm
Extend legs	32130.0000	*3.0L lever-action airpot	44.45cm
Extend legs	28696.0002	2.2L push-button airpot	45.72cm
Extend legs	13041.0001	2.5L push-button airpot	46.99cm
Extend legs	23300.0010	2.5L thermal server	46.99cm

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
39900.0007	WAVE 15-S-BF-APS	11 kg	220-230	8 - 8.5	1800-2000	50/60	I	Yes	
39900.0011	WAVE 15-S-APS	11 kg	100	12.5	1200	50/60			

Plumbing: 138-621 kPa. Machine supplied with 1/4" male flare fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

AXIOM® Airpot Brewers



AXIOM-APS

Medium volume brewing solution featuring simple operation, precise extraction control

- For high lime areas, BrewLOGIC® technology calculates flow rate and adjusts brew time to maintain consistent pot levels.
- BrewWIZARD® technology simplifies brewer programming.
- Brews directly into 1.9 to 3 litre airpots.
- Convenient airpots keep coffee hot for hours.
- Ensures coffee brew quality with cold brew lock out capability.
- Electronic diagnostics and built in tank drain for ease of service.
- Coffee extraction controlled with programmable pre-infusion, pulse brew and digital temperature control.
- Hot water faucet.
- Energy Saver Mode.

RELATED PRODUCTS

Regular Filter Pack

Product No.: 20115.0000



Gourmet Funnel Filter Pack

Product No.: 20157.0000



Gourmet Funnel

Product No.: 34559.0000



ED-17-TL

Product No.: 30201.1001

EQ-17-TL

Product No.: 30200.1000


Inlet Hose Assembly

Product No.: 32865.0001

Airpots sold separately
See page 21 for details



17



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
38700.0035	AXIOM-APS	16.3 kg	220 - 230	15.4 - 16	3400 - 3600	50/60	1	Yes	
38700.0036	AXIOM-APS		100	16	1600	50			
38700.0037	AXIOM-APS		230	15.7	3600	50/60			

Plumbing: 138-621 kPa. Machine supplied with 3/8" male flare fitting. All plumbed models that are CE listed feature backflow prevention.

Airpot Brewers



CWTF-APS

- Brews 14.6 to 28.4 litres of coffee per hour.
- Brews directly into 1.9 to 3 litre airpots.
- Convenient airpots keep coffee hot.
- Airpots are easily transported to remote meeting rooms, breakfast bars, etc.
- Pour-over model available.
- Pour-over feature included on automatics.
- Digital timer enables users to make brew cycle adjustments from the front panel.
- Gourmet funnel available for use with heavier throw weights of coffee.
- Hot water faucet on CWTF models.

RELATED PRODUCTS

Regular Filter Pack

Product No.: 20115.0000



Gourmet Funnel Filter Pack

Product No.: 20157.0000



Gourmet Funnel

Product No.: 34559.0000

ED-17-TL

Product No.: 30201.1001



EQ-17-TL

Product No.: 30200.1000


Inlet Hose Assembly











Product No.: 32865.0001



Airpots sold separately
See page 21 for details

18



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
POUROVER									
23001.0024	CWA-APS, pourover; no faucet, plastic funnel	12.7 kg	230	9.0	2075	50/60	I	No	CE   NSF
23001.0064	CWA-APS, pourover; no faucet, plastic funnel		220	8.6	1900	60			 NSF CE
23001.0074	CWA-APS, pourover; plastic funnel, Master On/Off		230	9.0	2075	50/60		UK Plug	CE NSF
23001.0079	CWA-APS, pourover; no faucet, Gourmet funnel		220	15.0	3300			EU Plug	
23001.0088	CWA-APS, pourover; no faucet							Yes	CE 
AUTOMATIC									
23001.0019	CWTF35-APS, plastic funnel	16.8 kg	230	14.2	3260	50/60	I	No	CE   NSF
23001.0021	CWTF35-APS, plastic funnel			9.0	2075				   NSF
23001.0065	CWTF35-APS, plastic funnel	15 kg	220	13.6	3000	60			 NSF CE
23001.0066	CWTF35-APS, plastic funnel	16.8 kg		8.6	1900				
Plumbing: 138-621 kPa. Machine supplied with 1/4" male flare fitting. All plumbed models that are CE listed feature backflow prevention.									

Plumbing: 138-621 kPa. Machine supplied with 1/4" male flare fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Twin Airpot Brewers



CWTF Twin APS

- Brews up to 56 litres of perfect coffee per hour.
- Convenient airpots keep coffee hot and are easily transported.
- Accommodates two 1.9 to 3.0 litre airpots.
- Equipped with tank drain.
- Gourmet funnel allows for heavier throw weights of coffee.
- Hot water faucet

RELATED PRODUCTS

Gourmet Funnel Filter Pack
Product No.: 20157.0000



EQHP-10
Product No.: 39000.0004





EQHP-10L
Product No.: 39000.0001

Inlet Hose Assembly
Product No.: 32865.0002



Airpots sold separately
See page 21 for details



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
23400.0044	CWTF TWIN-APS, gourmet funnel	29.1 kg	230	24	5500	50/60	I	Yes	CE NSF

Plumbing: 138-621 kPa. Machine supplied with 3/8" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Thermal Carafe Coffee Brewers



CWTF-TC

- Brews up to 22 litres of coffee per hour.
- Accepts thermal carafe up to 21.6cm tall.
- Use in quick-turn environment where high quality coffee is continuously refreshed.
- Pourover feature on automatic models.
- Hot water faucet on CWTF models

RELATED PRODUCTS

Regular Filter Pack
Product No.: 20115.0000





ED-17-TL
Product No.: 30201.1001



Inlet Hose Assembly
Product No.: 32865.0001

Thermal Carafes sold separately.
See page 21 for details



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
POUROVER									
23001.0067	CWA-TC, pourover; no faucet, plastic funnel	12.7 kg	230	9.0	2075	50/60	I	UK Plug	CE NSF PG V
AUTOMATIC									
I2950.0361	CWTFB-TC, plastic funnel	12.7 kg	100	15.5	1550	50/60	I	Yes	CE NSF PG NSF
I2950.0362	CWTFA-TC, plastic funnel	14.1 kg	230	9	2075	50		No	
I2950.0416	CWTFA-TC, plastic funnel		230	9.0	2075	50/60		UK Plug	

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Airpots and Thermal Carafes



Push-Button
Airpot



Lever-Action
Airpot



Thermal Pitcher



Thermal
Carafe



Economy
Thermal Carafe

PUSH-BUTTON AIRPOT

- Brew-through pump assembly - no need to remove for brewing.
- Just close the lid after brewing - dispenses up to 112 ml at the first pump.
- Glass insulation keeps beverage hot.
- Attractive, chrome finish with black trim.
- Available in 2.2 litre and 2.5 litre.

LEVER-ACTION AIRPOT

- Stainless steel lining ensures hot coffee for hours.
- Brew-through lid with lever-action for easy use.
- Available in 2.5 litre, 3.0 litre and 3.8 litre.

THERMAL CARAFE

- Holds 1.9 litres of coffee or other hot beverage.
- Unbreakable stainless steel interior and exterior.
- Superior vacuum insulation keeps beverages hot.
- Brew-through lid allows direct brewing.

THERMAL PITCHER

- Stainless steel lining ensures hot coffee for hours.
- Brew-through lid feature.
- Available in 1.9 liters

Product #	Description	Weight	Liner	Quantity	Capacity	Agency
28696.0002	2.2 litre Push-Button Airpot	2.04 kg	Glass	single unit	2.2 litre	
28696.0000	2.2 litre Push-Button Airpot	10.9 kg		6 units/case		
13041.0001	2.5 litre Push-Button Airpot	2.3 kg		single unit	2.5 litre	
13041.0101	2.5 litre Push-Button Airpot	11.3 kg		6 units/case		
32125.0000	2.5 litre Lever-Action Airpot	2.4 kg		single unit		3.0 litre
32125.0100	2.5 litre Lever-Action Airpot	14.6 kg		6 units/case		
32130.0000	3.0 litre Lever-Action Airpot	2.6 kg		single unit		
32130.0100	3.0 litre Lever-Action Airpot	15.9 kg		6 units/case		
36725.0000	3.8 litre Lever-Action Airpot	3.2 kg	Stainless Steel	single unit	3.8 litre	
36725.0100	3.8 litre Lever-Action Airpot	18.6 kg		6 units/case		
36029.0001	1.9 litre Thermal Carafe, black lid	1.36 kg		single unit	1.9 litre	
36029.0000	1.9 litre Thermal Carafe, black lid	15.4 kg		12/case		
36252.0001	1.9 litre Thermal Carafe, orange lid	1.36 kg		single unit		
36252.0000	1.9 litre Thermal Carafe, orange lid	15.4 kg		12/case		
40163.0000	1.9 litre Economy Thermal Carafe black lid	1.1 kg		single unit		
40163.0100	1.9 litre Economy Thermal Carafe black lid	13.6 kg		12/case		
40163.0001	1.9 litre Economy Thermal Carafe orange lid	1.36 kg		single unit		
40163.0101	1.9 litre Economy Thermal Carafe orange lid	12/case		12/case		
39430.0000	1.9 litre Deluxe Thermal Pitcher; black lid	1.36 kg		single unit		
39430.0100	1.9 litre Deluxe Thermal Pitcher; black lid	7.71 kg		6 units/case		

Thermal Server Coffee Brewers



CWTF - TS

- Brews up to 28 litres of coffee per hour.
- Accommodates 2.5L thermal server.
- Accommodates up to 10 cm tall cup.
- Pour-over feature included on automatic brewer models.
- Hot water faucet.

RELATED PRODUCTS

Regular Filter Pack
Product No.: 20115.0000



EQ-17-TL
Product No.: 30200.1000




ED-17-TL
Product No.: 30201.1001

Inlet Hose Assembly
Product No.: 32865.0001



Thermal servers sold separately
See pages 23 for details.



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
23000.0019	CWTFA35-TS, plastic funnel	15.4 kg	230	14.2	3260	50/60	1	No	CE PG
23000.0023	CWTFA20-TS, plastic funnel			9.0	2075				CE
23000.0031	CWTFA35-TS, plastic funnel		220	13.6	3000	60		Yes	CE NSF
23000.0033	CWTFB-TS, plastic funnel		100	12.9	1290	60			
23000.0034	CWTFB-TS, plastic funnel		200	18	3600	50/60		No	

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Thermal Coffee Servers and Stands



TSR-1 and TSR-2
(shown with TS servers no base)

THERMAL SERVER

- Convenient for keeping coffee hot for hours.
- Easily transported to remote locations.
- Depending on base, server can accommodate up to 16.51 cm cup.
- Glass-lined 2.5L capacity servers.

THERMAL SERVER RACK


- Holds one or two 2.5 litre thermal servers without base.
- Made of durable, easy-to-clean plastic.
- Drip trays to catch spills and keep serving areas clean.




TS Booster



TSR
(Raised)



TS with no base



TS with base

Product #	Description	Weight	Capacity	Quantity	Agency
23300.0007	TS, thermal server; single unit	2.7 kg	2.5 litres	single unit	
23300.0005	TS, thermal server; 6/case	15 kg	2.5 litres	6/case	
23300.0009	TS RAISED, thermal server; raised	2.7 kg	2.5 litres	single unit	
23300.0010	TS, thermal server; no base, single unit	1.8 kg	2.5 litres	single unit	
23300.0006	TS, thermal server; no base, 6/case	11.3 kg	2.5 litres	6/case	
22964.0000	BUNN safety-fresh lid (kit)	.5 kg		single unit	
18008.6001	TSR-1, thermal server rack, 1 position	2.1 kg		single unit	
18008.6002	TSR-2, thermal server rack, 2 position	3.6 kg		single unit	
18010.6000	Thermal server booster	.9 kg		single unit	



Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Titan™ Single Coffee Brewer and Server



Titan Single Brewer

High-volume brewing solution featuring simple operation, precise extraction control and portable servers

- Brews up to 85 litres of perfect coffee per hour.
- Coffee extraction controlled with pre-infusion and pulse brew; variable by-pass controls coffee strength.
- BrewMETER® allows automatic programming of pulse routine. 
- Funnel has 750 gram capacity and paper filter retainers to eliminate fold-over.
- Left or right faucet for hot water.
- Display in English, Spanish, or Katakana
- Large sprayhead.
- Energy Saver Mode. 
- Digital temperature control.

TITAN TF SERVER

- 12 litre capacity
- ThermoFresh® servers are insulated to keep coffee hot for hours.
- Large cup clearance allows for dispensing into cups, decanters and thermal carafes.
- Brew-through lid.
- Integrated sight gauge assembly allows for easy cleaning.
- Innovative fast flow faucet design.

RELATED PRODUCTS

Titan/Urn Filter Pack

Product No.: 20111.0000



Titan Funnel

Product No.: 40105.0000



EQHP-54

Product No.: 39000.0006



EQHP-54L

Product No.: 39000.0003



Inlet Hose Assembly


Product No.: 32865.0002




Flavour Label

Product No.: 41745.1000



Titan TF Server



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agencies
39300.0002	Titan Single	48.5 kg	230/400 230	16 32.0	11125 7360	50/60	3 1	No	 
39400.0001	Titan Server	5.4 kg							
Plumbing: 138-621 kPa. Machine supplied with 3/8" male flare fitting. All plumbed models that are CE listed feature backflow prevention.									


Plumbing: 138-621 kPa. Machine supplied with 3/8" male flare fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Titan™ Dual Coffee Brewer and Server



Titan Dual Brewer



High-volume brewing solution featuring simple operation, precise extraction control and portable servers

- Brews up to 120 litres of coffee per hour.
- Coffee extraction controlled with pre-infusion and pulse brew, digital temperature control, and large sprayhead; variable by-pass controls coffee strength.
- BrewMETER® allows automatic programming of pulse routine.
- Funnel has 750 gram capacity and paper filter retainers to eliminate fold-over.
- Left or right faucet for hot water.
- Display in English, Spanish, or Katakana.
- Large sprayhead.
- Energy Saver Mode.
- Digital temperature control.

TITAN TF SERVER

- 12 litre capacity
- ThermoFresh® servers are insulated to keep coffee hot and fresh for hours.
- Large cup clearance allows for dispensing into cups, decanters and thermal carafes.
- Brew-through lid.
- Integrated sight gauge assembly allows for easy cleaning.
- Innovative fast flow faucet design.

RELATED PRODUCTS

Titan/Urn Filter Pack
Product No.: 20111.0000



Titan Funnel
Product No.: 40105.0000



EQHP-54
Product No.: 39000.0006






EQHP-54L
Product No.: 39000.0003

Inlet Hose Assembly
Product No.: 32865.0002

Flavour Label
Product No.: 41745.1000



Titan TF Server



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
39200.0002	Titan Dual	67.1 kg	400 230	16 32.0	11125 7360	50/60	3 1	No	 
39200.0003			200	24.3	8400		3		
39400.0001	Titan Server	5.4 kg							

Plumbing: 138-621 kPa. Machine supplied with 3/8" male flare fitting. All plumbed models that are CE listed feature backflow prevention.


BrewWISE® Single ThermoFresh® DBC® Brewers




BrewWISE Single TF DBC

- Brews up to 43 2 litres of coffee per hour with three variable batch sizes.
- Stores individual coffee recipes.
- Large sprayhead and BrewWISE intelligence with pre-infusion and pulse brew for maximum flavour extraction. 
- Coffee strength controlled with variable by-pass.
- Wireless brewer-grinder interface via Smart Funnel® with SplashGard®. 
- Metric volume and Celsius temperature settings.
- Equipped with tank drain.

RELATED PRODUCTS


Single/Dual Filter Pack 
Product No.: 20138.0000

EQHP-10 
Product No.: 39000.0004


EQHP-10L 
Product No.: 39000.0001






BrewWISE Recipe Writer 
Product No.: 34444.0001

BrewWISE Recipe Card 
Product No.: 34447.0000

Inlet Hose Assembly 
Product No.: 32865.0002

ThermoFresh servers sold separately.
See page 28-29 for details.



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
34800.0009	SINGLETF DBC, black, funnel locks	26.8 kg	230	16.6	4000	50/60	I	No	    KSA
34800.0012	SINGLETF DBC, funnel locks								
34800.0013	SINGLETF DBC, black, funnel locks		200	18.5	3700	60			
34800.0016	SINGLETF DBC, funnel locks								



Plumbing: 138-621 kPa. Machine supplied with 3/8" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

BrewWISE® Dual ThermoFresh® DBC® Brewers



BrewWISE Dual TF DBC

- Brews up to 61.7 to 71.5 litres of coffee per hour with three variable batch sizes.
- Multi-phase brewer brews 65.5 to 98 litres of coffee per hour; and can be field converted to operate on either 3 phase or 1 phase.
- Stores individual coffee recipes.
- Large sprayhead and BrewWISE intelligence with pre-infusion and pulse brew for maximum flavour extraction. 
- Coffee strength controlled with variable by-pass.
- Wireless brewer-grinder interface via Smart Funnel® with SplashGard®. 
- Metric volume and Celsius temperature settings.
- Equipped with tank drain.

RELATED PRODUCTS

Single/Dual Filter Pack
Product No.: 20138.0000



EQHP-10
Product No.: 39000.0004




EQHP-10L
Product No.: 39000.0001








Inlet Hose Assembly
Product No.: 32865.0002



ThermoFresh servers sold separately
See page 28-29 for details.
See page 26 for additional related products.



NOTE: Catalog icon legend can be found on page 1.

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
34600.0011	DUAL TF DBC, funnel locks	41.96 kg	230	26.5	6100	50/60	1	No	    KSA
34600.0013	DUAL TF DBC, funnel locks		200	26.5	5300	60			
34600.0015	DUAL TF DBC, black, funnel locks		230	26.5	6100	50/60			
34600.0017	DUAL TF DBC, black, funnel locks		200		5300	60			
34600.0020	DUAL TF DBC, SST, 3 phase/1 phase, funnel locks, Master On/Off switch	42 kg	230 400	26.9 16	6200 11125	50/60	1 3	No	  
34600.0025	DUAL TF DBC, black, 3 phase/1 phase, funnel locks, Master On/Off switch		230 400	26.9 16	6200 11125		1 3		

Plumbing: 138-621 kPa. Machine supplied with 3/8" male fitting. All plumbed models that are CE listed feature backflow prevention.

Digital ThermoFresh® Servers and Stand



5.7 Litre TF Server

ThermoFresh servers hold beverages at optimum flavour profile for hours without requiring the energy consumption of traditional warming plates

- Four-hour digital count-up timer.
- Volume indicator display.
- Vacuum insulated.
- Unique lid design features a pour spout for easy emptying and cleaning.
- Contemporary styling and wrap program for maximum merchandising.
- Digital sight gauge has a count-up timer that begins to count-up in one minute increments to specifically display how long the brewed beverage has been stored. Operates on four AAA batteries with an average 1-year lifespan. Display shows low battery symbol.
- Translucent faucet guard provides increased visibility while dispensing.
- Brew-through lid.
- Soft grip handle for easy transportation.

TF SERVER WITH BASE

- Built-in drip tray is easily removed for cleaning or providing extra clearance for large vessels.
- Large cup clearance.
- Ideal for use with Single or Dual DBC Brewers.



Baseless 5.7 Litre TF Server

TF BASELESS SERVER



- 17.9 cm cup clearance.
- Ideal for use with the Infusion Coffee Brewer (ICB)
- Use with the TF Server Stand for easy dispensing. Product No. 39795.0000



TF Server Stand



Digital Sight Gauge with Count-up Timer

Product #	Description	Dimension	Weight	Cord Attached	Agency
42700.0000	DSG TF Server; 3.8 litre, SST	52.3cm H x 23.6cm W x 33cm D	6.8 kg		 
42700.0001	DSG TF Server; 3.8 litre, black				
42750.0000	DSG TF Server; 5.7 litre, SST	57.7cm H x 23.6cm W x 33cm D	7.3 kg		
42750.0001	DSG TF Server; 5.7 litre, black				
42700.0050	Baseless DSG TF Server; 3.8 litre, SST	32cm H x 23.1cm W x 32.3cm D	4.9 kg		
42700.0051	Baseless DSG TF Server; 3.8 litre, black				
42750.0050	Baseless DSG TF Server; 5.7 litre, SST	37.3cm H x 23.1cm W x 32.3cm D	5.4 kg		
42750.0051	Baseless DSG TF Server; 5.7 litre, black				
39795.0000	TF Server Stand	22.1cm H x 23.9cm W x 32.8cm D	1.9 kg		

ThermoFresh® Servers and Stand



5.7 Litre TF Server

ThermoFresh servers hold beverages at optimum flavour profile for hours without requiring the energy consumption of traditional warming plates

- Vacuum insulated.
- Easily transport coffee to remote locations.
- Fast flow faucet.
- Brew-through lid.

TF SERVER WITH BASE

- Built-in drip tray is easily removed for cleaning or providing extra clearance for large vessels.
- Large cup clearance.
- Ideal for use with Single or Dual TF DBC Brewers.

RELATED PRODUCTS

Flavour Label
Product No.: 41745.1000



Baseless 3.8 Litre TF Server

TF BASELESS SERVER

- Use with the TF Server Stand for easy dispensing. Product No. 39795.0000
- Ideal for use with the Infusion Coffee Brewer (ICB).



TF Server Stand

Product #	Model	Dimension	Weight	Cord Attached	Agency
39500.0000	TF Server; 3.8 litre, SST	52.8cm H x 23.6cm W x 33cm D	5.9 kg		
39500.0001	TF Server; 3.8 litre, black				
39550.0000	TF Server; 5.7 litre, SST	58.2cm H x 23.6cm W x 33cm D	6.4 kg		
39550.0001	TF Server; 5.7 litre, black				
39500.0004	Baseless TF Server; 3.8 litre, SST	32.5cm H x 23.1 cm W x 33.3cm D	5.9 kg		
39500.0005	Baseless TF Server; 3.8 litre, black				
39550.0004	Baseless TF Server; 5.7 litre, SST	37.8cm H x 23.1 cm W x 33.3cm D	6.4 kg		
39550.0005	Baseless TF Server; 5.7 litre, black				
39795.0000	Stand assembly, TF Server	22.1cm H x 23.9cm W x 32.8cm D	1.9 kg		



Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

BrewWISE® Single Soft Heat® DBC® Brewers



Single SH DBC

Soft Heat technology automatically manages heat in the server docking system to ensure optimum flavour profile for hours

- Brews up to 43.2 litres of coffee per hour with three variable batch sizes.
- Stores individual coffee recipes.
- Large sprayhead and BrewWISE intelligence with pre-infusion and pulse brew for maximum flavour extraction. 
- Coffee strength controlled with variable by-pass.
- Wireless brewer-grinder interface via Smart Funnel® with SplashGuard®. 
- Metric volume and Celsius temperature settings.

RELATED PRODUCTS

Single/Dual Filter Pack
Product No.: 20138.0000



EQHP-10
Product No.: 39000.0004



EQHP-10L
Product No.: 39000.0001

BrewWISE Recipe Writer
Product No.: 34444.0001



BrewWISE Recipe Card
Product No.: 34447.0000











Inlet Hose Assembly
Product No.: 32865.0001

One Position Drip Tray
For use with Single/Single SH
Product No.: 26830.0000



Soft Heat servers and stands sold separately.
See page 34 for details.



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
33600.0003	SINGLE SH DBC, funnel locks	26.8 kg	230	16.6	4000	50/60	I	No	    KSA
33600.0005	SINGLE SH DBC, 17 hole spray head		200	19	3800				
33600.0012	SINGLE SH DBC, funnel locks		220	12.7	2800	60			  

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.



Dimensions shown in centimetres. For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

BrewWISE® Dual Soft Heat® DBC® Brewers



Dual SH DBC

Soft Heat technology automatically manages heat in the server docking system to ensure optimum flavour profile for hours

- Brews up to 71.5 litres of coffee per hour with three variable batch sizes.
- Stores individual coffee recipes.
- Large sprayhead and BrewWISE intelligence with pre-infusion and pulse brew for maximum flavour extraction. 
- Coffee strength controlled with variable by-pass.
- Wireless brewer-grinder interface via Smart Funnel® with SplashGard®. 
- Metric volume and Celsius temperature settings.

RELATED PRODUCTS

Single/Dual Filter Pack
Product No.: 20138.0000



EQHP-10
Product No.: 39000.0004



EQHP-10L
Product No.: 39000.0001

BrewWISE Recipe Writer
Product No.: 34444.0001



BrewWISE Recipe Card
Product No.: 34447.0000











Inlet Hose Assembly
Product No.: 32865.0001

Two Position Drip Tray
For use with Dual/Dual SH
Product No.: 27150.0000



Soft Heat servers and stands sold separately.
See page 34 for details.



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
33500.0008	DUAL SH DBC, funnel locks	26.8 kg	230	26.9	6200	50/60	I	No	   
33500.0014	DUAL SH DBC, 17 hole spray head		200	28	5600				
33500.0021	DUAL SH DBC, funnel locks		220	25.5	5600	60			  

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Single® Soft Heat® Brewers



Single SH

- Brews up to 40.1 litres of coffee per hour with three variable batch sizes.
- Electronic grinder interface instructs G9T-2 grinder on exact amount of coffee for selected brew batch size.
- Soft Heat® server heat control automatically shuts off once target temperature is reached. Can be set to 79.4° - 87.8°C.
- Holds one 5.7 litre SH server; sold separately.
- Remote one or two server dock stations, sold separately.

RELATED PRODUCTS

Single/Dual Filter Pack
Product No.: 20138.0000



EQHP-10
Product No.: 39000.0004




EQHP-10L
Product No.: 39000.0001

Inlet Hose Assembly
Product No.: 32865.0001

One Position Drip Tray
For use with Single/Single SH
Product No.: 26830.0000



Soft Heat servers and stands sold separately.
See page 34 for details.



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
27800.0006	SINGLE SH	26.8 kg	230	13.5	3100	50/60	I	No	CE NSF
27800.0021			220	12.7	2800	60			CE NSF

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Dual® Soft Heat® Brewers



Dual SH

- Brews up to 61.7 litres of coffee per hour with three variable batch sizes.
- Multi-phase brewer brews 65.5 to 98.4 litres of perfect coffee per hour, and can be converted to operate on either 3 phase or 1 phase.
- Electronic grinder interface instructs grinder on exact amount of coffee for selected brew batch size.
- Soft Heat® server heat control automatically shuts off once target temperature is reached. Can be set to 79.4° - 87.8°C.
- Holds two 5.7 litre SH servers, sold separately.

RELATED PRODUCTS

Single/Dual Filter Pack
Product No.: 20138.0000



EQHP-10
Product No.: 39000.0004





EQHP-10L
Product No.: 39000.0001





Inlet Hose Assembly
Product No.: 32865.0001

Two Position Drip Tray
For use with Dual/Dual SH
Product No.: 27150.0000



Soft Heat servers and stands sold separately.
See page 34 for details.




Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
27900.0006	DUAL SH, mechanical thermostat	26.8 kg	230	26.9	6200	50/60	1	No	 
27900.0037	DUAL SH, mechanical thermostat		220	25.5	5600	60			
27900.0031	DUAL SH, 3 phase/1 phase, Master On/Off switch	40.9 kg	230 400	26.9 14.5	6200 10000	50/60	1 3	No	 

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.


Soft Heat[®] Servers and Stands




SH Server and ISH Stand



SH Server



ISH Stand




2SH Stand



2SH Stand

















Soft Heat technology automatically manages heat in the server docking system to ensure optimum flavour profile for hours

SH SERVER

- Soft Heat[®] servers supply controlled heat to coffee to maintain flavour and temperature.
- LED power indicator shows server is operational.
- Safety-Fresh[®] brew-through lid with vapour seal and spill prevention. 
- For use with Single/Dual SH and Single/Dual SH DBC

SH STAND

- Remote one and two server docking stations for additional satellite coffee serving.
- Docking stations have instant power contact with servers.

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency	
27850.0001	SH SERVER, 5.7 litre capacity, no flashing lamp	7.7 kg							 	
27850.0006	SH SERVER, 5.7 litre capacity, 45 minute									
27850.0009	SH SERVER, 5.7 litre capacity, adjustable timer									
27850.0016	SH SERVER, 5.7 litre capacity, 240 minute									
27850.0036	SH SERVER, 5.7 litre capacity, Korea									
27825.0001	ISH STAND, holds 1 SH server	5.9 kg	220/230	0.35	75	50/60	1	Yes	 	
27825.0002	ISH STAND, holds 1 SH server; UK plug							UK Plug	   	
27825.0015	SH STAND, holds 1 SH server; Korea									
27875.0001	2SH STAND, holds 2 SH servers	10 kg	220/230	0.7	150	50/60		Yes	 	
27875.0002	2SH STAND, holds 2 SH servers; UK plug							UK Plug	   	
27875.0013	2SH STAND, holds 2 SH servers; Korea							Yes		

Single[®] Brewers with Portable Server



Single
(server included)

- Brews 19.3 to 43.2 litres of coffee per hour with three variable batch sizes.
- Adjustable bypass ensures perfect coffee regardless of batch size.
- Upper hot water faucet on all models does not affect brew level.
- Electronic timer ensures fast set up and accurate brew levels.
- Electronic grinder interface instructs grinder on exact amount of coffee for selected brew batch size.
- 5.7 litre, 1.5 GPR portable server has Safety-Fresh[®] brew-through lid with vapour seal and spill protection.
- Equipped with tank drain.

RELATED PRODUCTS

Single/Dual Filter Pack
Product No.: 20100.0000



EQHP-10
Product No.: 39000.0004




EQHP-10L
Product No.: 39000.0001

Inlet Hose Assembly
Product No.: 32865.0001

One Position Drip Tray
For use with Single/Single SH
Product No.: 26830.0000



Additional GPR Portable servers and warmers.
See page 37 for details.



NOTE: Catalog icon legend can be found on page 1.

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
23050.0049	SINGLE, mechanical thermostat, stainless funnel	26.3 kg	230	13.7	3150	50/60	I	No	UL, CE, NSF
23050.0047	SINGLE, mechanical thermostat, stainless funnel		200	19.3	3850	50			NSF
23050.0058	SINGLE, mechanical, stainless funnel, Korea		230	13.7	3150	50/60			CE

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dual[®] Brewers with Portable Server



Dual
(servers included)

- Brews 61.7 to 71.5 litres of coffee per hour with three variable batch sizes.
- Adjustable bypass ensures perfect coffee regardless of batch size.
- Upper hot water faucet on all models does not affect brew level.
- Electronic timer ensures fast set up and accurate brew levels.
- Electronic grinder interface instructs grinder on amount of coffee for selected brew batch size.
- 5.7 litre, 1.5 GPR portable servers have a Safety-Fresh[®] brew-through lid with vapour seal and spill protection.
- Equipped with tank drain.

RELATED PRODUCTS

Single/Dual Filter Pack
Product No.: 20100.0000



EQHP-10
Product No.: 39000.0004




EQHP-10L
Product No.: 39000.0001

Inlet Hose Assembly
Product No.: 32865.0001

Two Position Drip Tray
For use with Dual/Dual SH
Product No.: 27150.0000



Additional GPR Portable servers and warmers.
See page 37 for details.



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
20900.0055	DUAL, mechanical thermostat, stainless funnel	44.5 kg	230	27.4	6300	50/60	I	No	
20900.0084	DUAL, mechanical, SST, Korea								

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.


Portable Servers and Warmers for Satellite Brewers



I GPR with RWS I


I.5GPR with RWS I

PORTABLE SERVER


- Models available with capacities up to 3.8 or 5.7 litres.
- Portable servers for remote service.
- Safety-Fresh® brew-through lid with vapour seal and spill protection. 

WARMER


- Models available to accommodate 3.8 or 5.7 litre servers.
- Legs are adjustable on RWS I.
- For use with Single and Dual.





RWS I



I 5GPR-FF
(top handles)



IGPR
(side handles)


Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
I2487.0001	I GPR SS, 3.8 litre, bail handle	3.9 kg							
I2487.0003	I GPR SS, 3.8 litre, side handle	3.9 kg							
I2487.0005	I GPR-FF, 3.8 litre, fast flow faucet, bail handle	4.1 kg							
20950.0004	I.5GPR-FF, 5.7 litre, fast flow faucet, top handle	4.5 kg							
I2203.0011	RWS I A	4.1 kg	230	0.5	118	50/60	I	No	
I2203.0012	RWS I B		100	0.9	91	50		Yes	

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

BrewWISE® Hot Beverage Systems



Single SH DBC

- Perfect for Hot Milk Tea or Hot Milk Coffee.
- Single brews up to 43.2 litres and Dual brews up to 71.5 litres of tea or coffee per hour with three variable batch sizes.
- Reduce accidents with safety features that decrease hot splashes from funnel, eliminate brewing when funnel or server is not present.
- Troubleshoot all switches and electrical components from the front panel with advanced diagnostic service tools.
- Consistently brew perfect tea using Digital Brewer Control with pulse brew. 
- Metric volume and Celsius temperature settings.
- Holds tea or coffee at just the right temperature for preparing superior Hot Milk beverages.

RELATED PRODUCTS

Single/Dual Filter Pack
Product No.: 20138.0000



EQHP-10
Product No.: 39000.0004



EQHP-10L
Product No.: 39000.0001


Soft Heat servers sold separately.
Product No.: 27850.0023
Specifically designed for use with Hot Beverage System
See page 34 for details.




One Position Drip Tray
For use with Single/Single SH
Product No. : 26830.0000










Two Position Drip Tray
For use with Dual/Dual SH
Product No. : 27150.0000



Single SH DBC



Dual SH DBC

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
33600.0006	SINGLE SH DBC, funnel lock	26.8 kg	230	19	4400	50/60	I	No	  
33600.0021				13.5	3100				
33500.0034	DUAL SH DBC, lower faucet	40.8 kg		26.9	6200				   

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.



Multi-Hopper Grinders

GRINDERS



MHG

A superior coffee grinding system combines the ability to grind multiple coffees with BrewWISE® Technology

- Convenient, front-loading hoppers. Allows grinding of a wide variety of coffees.
- Hoppers hold up to 2.75 kg each of regular, decaf or speciality beans.
- Stores individual coffee grind weight profiles.
- Portion controlled for the right amount of coffee, with three batch sizes per hopper.
- Precision burrs for consistent, commercial quality grind.
- Easy-to-clean removable hoppers.
- LCD alphanumeric display shows coffee names and diagnostics.
- Accommodates all BrewWISE® Smart Funnels®. 
- BrewWISE® intelligence means the Smart Hopper manages the grinding and brewing process from start to finish. 
- Smart Hopper tells the grinder what coffee is in it through a microchip in the hopper.

RELATED PRODUCTS

2 Position Rack

Product No.: 36760.0000



4 Position Rack

Product No.: 36760.0001



Hopper/Lid Assembly

Product No.: 36845.0000



Hopper Partition

Product No.: 36053.0000


BrewWISE Recipe Writer

Product No.: 34444.0001





BrewWISE Recipe Card

Product No.: 34447.0000



MHG

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
35600.0001	MHGA	31.8 kg	230	4.5	920	50	I	Yes	 
35600.0003	MHGA, black		230	4.5	920	50			
35600.0005	MHGB		100	9	900	60			
35600.0008	MHGB					60			

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Weight Driven Grinder




G9WD-RH


Weight-based, portion-control for the right amount of coffee every time, with 3 batch sizes

- Unparalleled grind weight accuracy.
- Hopper holds up to 2.72 kg.
- Precision burrs for consistent, commercial quality grind.
- LCD alphanumeric display shows machine status and diagnostics.
- Removable hopper for easy cleaning.

40



G9WD-RH

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
40700.0004	G9WD-RH	31.8 kg	230	4.5	1035	50	I	Yes	 


Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Portion Control Grinders with 1 Hopper



- Single hopper holds 4.1 kg of coffee.
- Portion controlled for the right amount of coffee every time.
- Precision burrs for consistent, commercial-quality grind.
- Accommodates larger brewer funnels.
- Three-year warranty on grinding burrs.

G9T HD, Tall



NOTE: Catalog icon legend can be found on page 1.

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
05800.0023	G9TA HD, tall	39.5 kg	230	4.5	1035	50	1	Yes	CE

Portion Control Grinders with 2 Hoppers




G9-2T DBC

PORTION CONTROL GRINDER

- Two hoppers hold 2.7 kg each.
- Selected models interface to compatible BUNN brewers with interface cable.
- Portion controlled for the right amount of coffee every time.
- Precision burrs for consistent, commercial-quality grind.

BREWWISE® DBC GRINDER


- Two hoppers hold 2.7 kg each.
- Stores individual coffee grind profiles.
- Operate any combination of BrewWISE® equipment error-free with wireless brewer-grinder interface via Smart Funnel®. 
- Portion controlled for the right amount of coffee every time with 3 batch sizes per hopper.

RELATED PRODUCTS



Interface Cable

Product No.: 05188.0002

42



G9-2T

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
24250.0022	G9-2TA HD, interface	32.2 kg	230	4.5	1035	50	I	Yes	
33700.0005	G9-2TA DBC	30.4 kg	230	4.5	1035	50			
33700.0007	G9-2TB DBC		100	9.4	940			No	
33700.0009	G9-2TA DBC, black		230	4.5	1035				

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Low Profile Portion Control Grinders



LPG

- Professional grind provided by large 81 mm diameter burrs.
- Powered by quiet, high-torque motor.
- Large, clear bean hopper merchandises 2.75 kg of fresh coffee beans.


LPG-2 FEATURES

- Two 1.36 kg hoppers allow for regular and decaf or speciality beans.




LPG-2E




43



LPG



LPG-2E

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
20580.0005	LPG	10 kg	100	4	400	50	I	Yes	
20580.0006	LPGA	10.4 kg	230	1.5	360	50/60			
20580.0014	LPGA	10.5 kg	220-230						
26800.0004	LPGA-2E	12.5 kg	220-230						

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

French Press Portion Control Grinders



FPG GRINDER

- Accommodates up to 20.3 cm tall cafetière or funnel for drip-style brewer.
- Multi-batch setting allows users to specify a French press brew size or grind enough coffee into a funnel to brew up to 3.0 litres of drip-style coffee.
- Single hopper holds 2.72 kg of beans.
- Large commercial 81 mm diameter burrs provide maximum grinding precision for small amounts of coffee.
- Quiet, low speed, high torque motor.
- Can accommodate gourmet funnel for heavier throw weights.


FPG-2 DBC GRINDER

- Digital touch pad for front of machine programming and LCD readout.
- Two hoppers hold 1.36 kg each of beans.



FPG

FPG-2 DBC
(cafetière not available)



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
36800.0001	FPGA, black	13.4 kg	230	1.5	360	50/60	I	Yes	<div> <div>CE</div> <div>KSA</div> </div>
36800.0002	FPGA		220			60			
36800.0004	FPGA, SST		100	3.6		50			
36400.0002	FPG-2 DBC		230	1.5					<div> <div>CE</div> <div>CE</div> </div>
36400.0003	FPGA-2 DBC								

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Bulk Coffee Grinders




G2 HD

G2, G3 HD GRINDERS

- G2 hopper holds .91 kg of fresh coffee beans.
- G3 hopper holds 1.36 kg of fresh coffee beans.
- Turbo action draws coffee through grind chamber for greater grinding efficiency.
- Fast grinding .45 kg in under 30 seconds.
- Wide range of grinds can be selected.
- Convenient cleaning lever ensures complete clean out of coffee from grind chamber.
- Bag switch stops motor when bag is removed and prevents grinding before bag is in place.
- Heavy-duty precision burrs for quality, finer grinds.

G2 trifecta™ GRINDER

- Chute assembly accommodates trifecta brew cup.
- Expanded range of precise grinds can be selected.
- May be used as a bulk grinder in behind-the-counter applications.
- Hopper holds .91 kg of fresh coffee beans.



G2/G3 HD



G2 trifecta



G3 HD

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
22102.0005	G2A HD, Turkish burrs, black	27.7 kg	230	4.5	1035	50	1	Yes	CE
41900.0001	G2 trifecta	26.8 kg	100						
41900.0002	G2 trifecta		230						
22100.0006	G3A HD, black		220		990	60			KSA
22100.0008	G3A HD, black								
22100.0013	G3A HD, black, Korea								

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Liquid Coffee Ambient Systems



LCA-2 PC

Coffee-On-Demand dispenser meets the requirements of banquets, convention centers, and hotels

- Attractive, narrow unit.
- Easy to program, one-touch portion control for self-serve applications.
- Accommodates 2 litre and most 4 litre bag-in-box (BIB) containers.
- Insulated product cabinet assures maximum product life.
- FlavorGard® technology continuously monitors extract-to-water ratio and assures flavour consistency.
- Dispenses easily into carafes by flipping tray.
- Equipped with tank drain.
- Hot water dispense.

RELATED PRODUCTS

EQHP-10

Product No.: 39000.0004



EQHP-10L

Product No.: 39000.0001

EQHP-25

Product No.: 39000.0005



EQHP-25L

Product No.: 39000.0002

Inlet Hose Assembly

Product No.: 32865.0002

1/8" Replacement Tube Kits

Product No.: 34728.1000



3/16" Replacement Tube Kits

Product No.: 34727.1000



Scholle BIB connector

Product No.: 35057.0000




LiquiBox QC/D II BIB connector

Product No.: 35055.0000



NOTE: Catalog icon legend can be found on page I.



Product #	Description	Dispense Rate/Sec.		Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
		1.8 oz.	2.5 oz.								
36500.0009	LCA-2A, PC, 1/8" Scholle Kit	45:1 - 100:1	65:1 - 100:1	37.2 kg	230	16	3800	50/60	1	No	CE
36500.0010	LCA-2A, PC, 3/16" Scholle Kit	25:1 - 45:1	25:1 - 65:1								
36500.0013	LCA-2A, PC, 1/8" Scholle Kit	45:1 - 100:1	65:1 - 100:1			26	6000				
36500.0014	LCA-2A, PC, 3/16" Scholle Kit	25:1 - 45:1	25:1 - 65:1								
36500.0059	LCA-2A, PC, 3/16" Scholle Kit	25:1 - 45:1	25:1 - 65:1			13	3000				

Plumbing: 140-620 kPa. Machine supplied with 3/8" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres. For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Liquid Coffee Refrigerated Systems



LCR-2 PC

Coffee-On-Demand dispenser meets the requirements of banquets, convention centers, and hotels

- Refrigerated product cabinet extends product flavour profile, maintains 3.3 – 5.5° C in product compartment.
- Attractive, narrow unit.
- Easy to program, one-touch portion control for self-serve applications.
- Accommodates 2 litre and most 4 litre bag-in-box (BIB) containers.
- FlavorGard® technology continuously monitors extract-to-water ratio and assures flavour consistency.
- Dispenses easily into carafes by flipping tray.
- Equipped with tank drain.
- Hot water dispense.

RELATED PRODUCTS

EQHP-10

Product No.: 39000.0004



EQHP-10L

Product No.: 39000.0001

EQHP-25

Product No.: 39000.0005



EQHP-25L

Product No.: 39000.0002

Inlet Hose Assembly

Product No.: 32865.0002

1/8" Replacement Tube Kits

Product No.: 34728.1000



3/16" Replacement Tube Kits

Product No.: 34727.1000




Scholle BIB connector

Product No.: 35057.0000



LiquiBox QC/D II BIB connector

Product No.: 35055.0000



Product #	Description	Dispense Rate/Sec.		Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
		1.8 oz.	2.5 oz.								
36500.0040	LCR-2A, PC, 1/8" Scholle Kit	45:1 - 100:1	65:1 - 100:1	51.7 kg	230	16	3800	50/60	1	No	CE
36500.0041	LCR-2A, PC, 3/16" Scholle Kit	25:1 - 45:1	25:1 - 65:1			26	6000				
36500.0042	LCR-2A, PC, 1/8" Scholle Kit	45:1 - 100:1	65:1 - 100:1		230	13	3000		1		CE
36500.0043	LCR-2A, PC, 3/16" Scholle Kit	25:1 - 45:1	25:1 - 65:1			26	6000		1		
36500.0054	LCR-2A, PC, 1/8" Scholle Kit, Multi Phase	45:1 - 100:1	65:1 - 100:1			13	9000		3		
36500.0055	LCR-2A, PC, 3/16" Scholle Kit, Multi Phase	25:1 - 45:1	25:1 - 65:1			13	9000		3		
36500.0057	LCR-2A, PC, 3/16" QCD Kit	25:1 - 45:1	25:1 - 65:1		230	16	3800		1		


Plumbing: 140-620 kPa. Machine supplied with 3/8" male fitting. All plumbed models that are CE listed feature backflow prevention.

Infusion Series® Iced Tea and Coffee Brewers



ITCB

Space-saving combination brewer yields a variety of beverages with simple operation and precise extraction control

- Brew three beverages (iced tea, hot tea, hot coffee) from one model.
- Back-to-back brewing capability and allows 1.4 to 18.9 litre tea batches.
- Brews 17-28 litres of hot coffee per hour.
- Brews into most BUNN iced tea dispensers, 1.9 to 3.8 litre airpots, and 1.9 litre thermal carafes.
- BrewWISE® intelligence. 
- Alphanumeric display communicates advertising messages and machine status in English, Spanish and Katakana.
- Brew counter keeps track of batches brewed.
- Can brew full or half batches.
- Additional iced coffee recipe included.
- Equipped with tank drain.
- Black plastic coffee funnel and separate tea funnel.
- Integrated flip tray converts to three positions: thermal carafe, airpot and tea dispenser.

RELATED PRODUCTS

Tea Filter Pack

Product No.: 20100.0000



Stainless Steel Smart Funnel®

Product No.: 32643.0000




Inlet Hose Assembly

Product No.: 32865.0001



Tea Dispensers sold separately. See pages 50 for details.

Airpots and Thermal Carafes sold separately. See page 21 for details.



ITCB	Tea Dispensers
25.75" trunk	TD4, TDS-3, TDO-3.5, TDO-4
29" trunk	TD4, TD4T, TDO-3.5, TDO-4, TDO-5, TDO-N-3.5, TDO-N-4

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
35700.0022	ITCBA, 25.75" (65.4 cm), with tray	22.7 kg	230	14	3200	50/60	I	No	CE
35700.0026	ITCBA, 25.75" (65.4 cm) with tray		200	17.5	3500	50			CE
35700.0029	ITCBA, 29" (73.7 cm), with tray		230	14	3200	50/60			CE

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Iced Tea Brewers



TB3

Fresh iced tea brewing solution with simple operation for a wide variety of dispensers

TB3 AND TB3Q

- Brews 61.7 to 101.1 litres per hour from tea leaves.
- Brews directly into any style server.
- Meet your volume needs; brew 11.6 litres of iced tea at a time.
- Quickbrew (Q) models available for shorter brewing cycles.

LOW PROFILE TEA BREWER

- Brews directly into TDO-3.5 dispenser with brew-through lid.
- Sleek, compact, low-profile styling to accommodate a variety of spaces.
- Quickbrew (Q) for shorter brewing cycle.

RELATED PRODUCTS

Tea Filter Pack

Product No.: 20100.0000



Inlet Hose Assembly


Product No.: 32865.0001




Tea Dispensers sold separately.
See pages 50 for details.






TB3Q LP



TB3, TB3Q



TB3Q LP

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
36700.0046	TB3B, 25.75" (65.4 cm), ready light, 1/2 batch, 2 fnls	19.5 kg	100	17.2	1718	50/60	1	No	
36700.0062	TB3QA, 25.75" (65.4 cm) trunk	18.6 kg	230	8	1800			Yes	
36700.0063	TB3A, 29" (73.7 cm) trunk	11.2 kg							
36700.0084	TB3A, 25.75" (65.4 cm) trunk	11.2 kg							
36700.0105	TB3QA-LP, low profile	19.5 kg							

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Iced Tea Dispensers



TD4

TD4T

TDO-3.5

TDO-4



TDO-5

TDS-3

TDS-3.5



TDO-N-3.5

TDO-N-4

SQUARE ICED TEA DISPENSER

- Dispensers have 15.14 litre capacity.
- Sight gauges shows tea volume.
- Available with solid or brew-through lids.

CYLINDER STYLE DISPENSER


- Dispensers available in 13.2, and 15.1 litres.
- Sump dispense valve assures complete dispensing of tea.
- TDO-5, TDO-4, and TDO-3.5 models have plastic lid and oval shape.
- Handles labeled "sweetened" and "unsweetened".
- Handles are mounted offset for closer side-by-side positioning.

NARROW ICED TEA DISPENSER

- Dispensers have 15.14 litre capacity.
- Two dispensers, placed side-by-side, allow added flexibility and twice the capacity within the same footprint as one TDO-4.
- Front - back handles for reduced counterspace usage.

TB3/TB3Q	Tea Dispensers
25.75" trunk	TD4, TDS-3, TDO-4
29" trunk	TD4, TD4T, TDS-3, TDS-3.5, TDO-4, TDO-5, TDO-N-3.5, TDO-N-4

ITCB	Tea Dispensers
25.75" trunk	TD4, TDS-3, TDO-3.5, TDO-4
29" trunk	TD4, TD4T, TDS-3, TDO-3.5, TDO-4, TDO-5, TDO-N-3.5, TDO-N-4

Product #	Description	Weight	Dimensions	Cord	Agency
03250.0003	TD4, sight gauge, solid lid	5.4 kg	43.4cm H x 23.1cm W x 39.9cm D		
03250.0006	TD4, brew-through lid	5.0 kg			
03250.0004	TD4T, sight gauge, solid lid, tall	5.9 kg	55.9cm H x 23.1cm W x 39.9cm D		
03250.0005	TD4T, brew-through lid, tall	5.9 kg			
03250.0018	TD4T, brew-through lid, tall, no decal	5.9 kg			
34100.0000	TDO-4, solid lid	5.4 kg	48.3cm H x 27.2cm W x 34.8cm D		
34100.0001	TDO-5, solid lid	6.4 kg	55.9cm H x 27.2cm W x 34.8cm D		
34100.0002	TDO-4, brew-through lid	5.4 kg	48.3cm H x 27.2cm W x 34.8cm D		
34100.0003	TDO-5, brew-through lid	6.4 kg	55.9cm H x 27.2cm W x 34.8cm D		
37100.0000	TDO-3.5, low profile, brew-through lid	4.5 kg	25.4cm H x 24.9cm W x 40.9cm D		
33000.0000	TDS-3	9.4 kg	48.3cm H x 24.9cm W x 32.5cm D		
33000.0008	TDS-3.5	10 kg	51.8cm H x 24.9cm W x 32.5cm D		
39600.0001	TDO-N-3.5	5.6 kg	54.9cm H x 15.7cm W x 34.3cm D		
39600.0002	TDO-N-4	5.6 kg	53.3cm H x 15.2cm W x 60cm D		
37675.0001	LP Server Stand	3.9 kg	23.5cm H x 29.2cm W x 35.6cm D		

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Tea Concentrate Dispensers




TCD-1



- Venturi valve creates siphon that pulls product through to mixing valve.
- Rear shut-off valve for cleaning dispenser.
- Accepts 3.8 litre jugs in top of container or bag-in-box.
- Side off-set handles for side-by-side placement to conserve space.
- Built-in pressure regulator provides consistent product to water ratio.
- Mixes a range of 5:1 to 15:1 concentrate to water ratio.
- Solid plastic lid.
- For use with tea concentrates only.

RELATED PRODUCTS


Drip Tray
Product No.: 38029.1000



TCD-1



TCD-2



TCD-2

Product #	Description	Weight	Agency
37750.0000	TCD-1	7.8 kg	NSF
37750.0002	TCD-2	8.9 kg	NSF


iMIX® Dispensers with 3 Hoppers



iMIX-3 PC

Sleek, eye-catching powdered beverage dispenser featuring advanced mixing technology delivers exceptional hot drinks

iMIX 3

- Three, 3.6 kg hoppers
- Lighted front graphics for merchandising.
- Large 16.66 litre hot water tank.
- Cup clearance of 18.4 cm.
- High speed, heavy-duty whipper for complete product mixing.
- Front of machine access for easy service, set up and calibration.
- Variable speed motors allow control of product consistency (.75 to 6.6 grams of powder per second).
- Low powder product detection system.**
- Alphanumeric display in English and Spanish.*
- Spring-loaded, all metal auger drive system for easy hopper installation.
- RPM feedback.** 

*Available only on iMIX-3 and iMIX-3S+.

**Available only on iMIX-3.

iMIX-3S+

- Can be set as push and hold or single size portion control.
- Alphanumeric display allows adjustments and service operational testing from front of machine. Also communicates advertising messages, machine status and technical support contact information.

RELATED PRODUCTS

EQHP-10

Product No.: 39000.0004



EQHP-10L

Product No.: 39000.0001

Inlet Hose Assembly

Product No.: 32865.0001

Chai Display

Product No.: 37457.0001



Steamer Display

Product No.: 37457.0003




Hot Chocolate Display

Product No.: 37457.0002



iMIX-3S+



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
36900.0014	iMIX-3A, portion control	40.8 kg	230	15	3600	50	I	No	CE
36900.0027	iMIX-3B, portion control, non-lighted display		200	12.7	2530	50/60			
38600.0004	iMIX-3S+A, pushbutton		230	15	3600	50			CE



Plumbing: 138-624 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

iMIX® Dispensers with 4 and 5 Hoppers



iMIX-4 PC



Sleek, eye-catching powdered beverage dispenser featuring advanced mixing technology delivers exceptional hot drinks

iMIX-4 FEATURES

- Four, 3.6 kg hoppers
- Lighted front graphics for merchandising.
- Large 27.63 litre hot water tank.
- Cup clearance of 18.4 cm.
- Variable speed motors allow control of product consistency in mixing chamber (.75 to 6.6 grams of powder per second).
- High speed, heavy-duty whipper.
- Front of machine access for easy service, set up and calibration.
- Spring-loaded, all metal auger drive system for easy hopper installation.
- Low powder product detection system.
- Digital technology adds night mode to prevent pilferage.
- Alphanumeric display in English and Spanish.
- RPM feedback.
- Key service components easily accessible through front, top and side.

iMIX-5S+ FEATURES

- Large 26.5 litre hot water tank.
- Can be set as push and hold or single size portion control.
- Night mode to prevent pilferage.
- Alphanumeric display in English and Spanish.

RELATED PRODUCTS

EQHP-10
Product No.: 39000.0004

EQHP-10L
Product No.: 39000.0001


Inlet Hose Assembly
Product No.: 32865.0001



NOTE: Catalog icon legend can be found on page 1.



iMIX-5S+

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
37000.0009	iMIX-4A, portion control	59.9 kg	230	15	3600	50	I	No	
38100.0005	iMIX-5S+A, pushbutton	60 kg	230		3600	50			

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Fresh Mix Dispensers with 1 and 2 Hoppers



FMD-2


- Capacity:
FMD-1: One, 3.6 kg hopper
FMD-2: Two, 1.81 kg hoppers
- Variable speed hopper motor offers a wide range of product mix ratios (1.5 to 12 grams of powder per second).
- Lighted graphics merchandise drinks for maximizing profits.
- Large hot water reservoir provides 15.9 litre/hour serving capacity.
- Adjustable legs and drip tray allow up to 17.8 cm opening for serving cup.
- Specially designed mixing system delivers perfect beverages every time.
- Improved automatic rinse reduces run-on after beverage is dispensed.

RELATED PRODUCTS

EQHP-10
Product No.: 39000.0004

EQHP-10L
Product No.: 39000.0001

Inlet Hose Assembly
Product No.: 32865.0001



FMD-1

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
SET00.0250	FMDA-1, black	34 kg	230	7.8	1800	50	1	Yes	CE
SET00.0252	FMDA-2, black	36.7 kg							

Plumbing: 138-690 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Fresh Mix Dispensers with 3 Hoppers



FMD-3 DBC

- Three 1.8l kg hoppers.
- Variable speed hopper motors offer control of product consistency.
- Lighted graphics for merchants.
- Adjustable legs and drip tray allow up to 17.8 cm opening for serving cup.
- Specially designed mixing system delivers perfect beverages every time.
- Improved automatic rinse reduces run-on after beverage is dispensed.

FMD DBC DISPENSER

- Easy-to-program, one-touch portion control for three cup sizes.
- Fast fill - perfect for quick service applications.
- Each mixing chamber has independent powder to water ratio.
- System setup is password protected for safety and security.
- Simple setup and hopper throw calibration system.
- Hot water dispense.

RELATED PRODUCTS

EQHP-10


Product No.: 39000.0004

EQHP-10L


Product No.: 39000.0001

Inlet Hose Assembly

Product No.: 32865.0001



FMD-3

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
28200.0048	FMDA-3, stainless steel	39.9 kg	230	15	3600	50/60	I	Yes	
29250.0010	FMDA-3 DBC, hot water dispense	39.9 kg	230		3600	50/60			
SET00.0174	FMDA-3 DBC, hot water disp., German literature								

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Fresh Mix Dispensers with 5 Hoppers



FMD-5

- Five 1.8l kg hoppers.
- Variable speed hopper motors offer a wide range of product mix ratios (1 5 to 12 grams of powder per second).
- Lighted graphics.
- Adjustable legs and drip tray allow up to 17.8 cm opening for serving cup.
- Specially designed mixing system delivers perfect beverages every time.
- Improved automatic rinse reduces run-on after beverage is dispensed.
- Electrical and plumbing components easily accessible through front and top.


RELATED PRODUCTS

EQHP-10
Product No.: 39000.0004



EQHP-10L
Product No.: 39000.0001

Inlet Hose Assembly
Product No.: 32865.0002



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
34900.0010	FMD-5A, push-hold	53.5 kg	230	15	3600	50/60	I	Yes	CE


Plumbing: 138-621 kPa. Machine supplied with 3/8" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.



JDF-2S

Cold beverage dispenser with High Intensity® mixing delivers superior drinks consistently

- One dispenser delivers both frozen and ambient products.
- Quick dispense with 44.4 to 59.2 ml per second flow rate.
- 20.8 cm cup clearance accommodates most juice containers.
- 4.5 kg ice bank assures cold product.
- Drink consistency and quick dispense assured by the High Intensity® mixing chamber's "stay clean" valve design. 
- Pumps and mixes 4:1 high viscosity and 5:1 juices accurately and consistently.
- Advanced concentrate pump designed for easy setup, accuracy and durability.
- Equipped with tank drain.
- Dual dispense allow simultaneous dispense from both dispense heads (*juice display only*).

RELATED PRODUCTS

EQHP-10
Product No.: 39000.0004





EQHP-10L
Product No.: 39000.0001

Inlet Hose Assembly
Product No.: 32865.0002

Refillable juice container
Product No.: 39302.0000
(sold separately)





Ambient concentrate conversion kit
Product No.: 33699.0001
(sold separately)



JDF-2S

*24°C incoming water for 190 drinks without exceeding 4.4°C finished drink temperature.


Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
NON-LIGHTED DOOR									
37900.0003	JDF-2SA, pushbutton	46.7 kg	230	4	920	50/60	I	Yes	 
37900.0007	JDF-2SA, pushbutton, iced coffee display								

Plumbing: 138-690 kPa. Machine supplied with 3/8" male fitting. All plumbed models that are CE listed feature backflow prevention.



Cold Beverage Systems




JDF-2S LD



JDF-2S PC LD
(Lighted door with portion control)



Cold beverage dispenser with High Intensity mixing delivers superior drinks consistently

- One dispenser delivers both frozen and ambient products.
- Quick dispense with 44.4 to 59.2 ml per second flow rate.
- 20.8 cm cup clearance accommodates most juice containers.
- 4.5 kg ice bank assures cold product.
- Drink consistency and quick dispense assured by the High Intensity® mixing chamber's "stay clean" valve design. 
- Pumps and mixes 4:1 high viscosity and 5:1 juices accurately and consistently.
- Advanced concentrate pump designed for easy setup, accuracy and durability.
- Equipped with tank drain.
- Three size portion control model available (*juice only*).
- Dual dispense allow simultaneous dispense from both dispense heads (*juice display only*).
- Lighted door units use high efficiency LED lighting.

RELATED PRODUCTS

EQHP-10

Product No.: 39000.0004



EQHP-10L

Product No.: 39000.0001

Inlet Hose Assembly

Product No.: 32865.0002

Refillable juice container

Product No.: 39302.0000

(sold separately)



Ambient concentrate conversion kit


Product No.: 33699.0001

(sold separately)



JDF-2S LD

*24°C incoming water for 190 drinks without exceeding 4.4°C finished drink temperature.

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
LIGHTED DOOR									
37900.0010	JDF-2SA, pushbutton	46.7 kg	230	4	920	50/60	I	Yes	
37900.0011	JDF-2SA, pushbutton, iced coffee display								
37900.0017	JDF-2SA, portion control								

Plumbing: 138-690 kPa. Machine supplied with 3/8" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.


Cold Beverage Systems

COLD BEVERAGE SYSTEMS



JDF-4S

Cold beverage dispenser with High Intensity mixing delivers superior drinks consistently

- One dispenser delivers both frozen and ambient products.
- Frost-free refrigerated compartment holds up to 15.1 litres of frozen concentrate.
- 8.2 kg ice bank assures cold product.
- Drink consistency and quick dispense assured by the High Intensity® mixing chamber's "stay clean" valve design. 
- Pumps and mixes 4:1 high viscosity and 5:1 juices accurately and consistently.
- Advanced concentrate pump designed for easy setup, accuracy and durability.
- Equipped with tank drain.
- Cold water feature on some models.

RELATED PRODUCTS

EQHP-10

Product No.: 39000.0004



EQHP-10L

Product No.: 39000.0001

Inlet Hose Assembly

Product No.: 32865.0002

Refillable juice container

Product No.: 39302.0000



(sold separately)



Ambient concentrate conversion kit

Product No.: 33699.0001

(sold separately)



NOTE: Catalog icon legend can be found on page 1.



JDF-4S

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
NON-LIGHTED DOOR									
37300.0001	JDF-4SA, pushbutton, juice display	58.5 kg	230	4	920	50/60	1	Yes	CE 
37300.0003	JDF-4SA, pushbutton, juice display, cold water dispense		230	4	920	50/60			CE
37300.0018	JDF-4SA, pushbutton, iced coffee display		230	4	920	50/60			CE 
37300.0021	JDF-4SA, pushbutton, iced coffee display, cold water dispense		230	4	920	50/60			CE


Plumbing: 138-690 kPa. Machine supplied with 3/8" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.



Cold Beverage Systems



JDF-4S LD




JDF-4S PC LD
(Lighted door with portion control)



JDF-4S LD

Cold beverage dispenser with High Intensity mixing delivers superior drinks consistently

- One dispenser delivers both frozen and ambient products.
- Frost-free refrigerated compartment holds up to 15.1 litres of frozen concentrate.
- 8.2 kg ice bank assures cold product.
- Drink consistency and quick dispense assured by the High Intensity® mixing chamber's "stay clean" valve design. 
- Pumps and mixes 4:1 high viscosity and 5:1 juices accurately and consistently.
- Advanced concentrate pump designed for easy setup, accuracy and durability.
- Equipped with tank drain.
- Cold water feature on some models.
- Three size portion control, lighted door models available. (juice only)
- Lighted door units use high efficiency LED lighting.

RELATED PRODUCTS

EQHP-10

Product No.: 39000.0004



EQHP-10L

Product No.: 39000.0001

Inlet Hose Assembly

Product No.: 32865.0002

Refillable juice container

Product No.: 39302.0000

(sold separately)



Ambient concentrate conversion kit

Product No.: 33699.0001

(sold separately)

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
LIGHTED DOOR									
37300.0005	JDF-4SA, pushbutton, juice display, lighted door	58.5 kg	230	4	920	50/60	1	Yes	NSF CE
37300.0007	JDF-4SA, pushbutton, juice display, lighted door; cold water dispense								CE
37300.0022	JDF-4SA, pushbutton, iced coffee display, lighted door								NSF CE
37300.0024	JDF-4SA, portion control, juice display, lighted door								

Plumbing: 138-690 kPa. Machine supplied with 3/8" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Ultra® Gourmet Ice® Systems




Ultra-2

Frozen beverage dispenser with reversing auger technology for superior mixing and freezing


- Reversing auger design quickens freeze time and reduces air mixing with product.
- Two large 11.4 litre hoppers for optimum cooling and serving capacity.
- Very simple to program and run with touchpad display, which also guides cleaning and preventive maintenance.
- Internally monitored refrigeration system to ensure long lasting performance.
- Lighted displays for merchant graphics.
- English/Spanish/French display.
- Autofill models (AFI) include autofill hoppers and factory installed liquid autofill kit for use with third party brix pumps.














Ultra-1



Ultra-1



Ultra-2

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
39800.0001	Ultra-1A, white/stainless	34.7 kg	230	4	600	50	I	Yes	  
39800.0003	Ultra-1A, black/stainless								
39800.0005	Ultra-1A, black								
39800.0006	Ultra-1B, black/stainless								
39800.0009	Ultra-1B, white/stainless								
34000.0002	Ultra-2A, all black	62.1 kg	220-230	8.8	1800	50/60	I	Yes	   
34000.0003	Ultra-2A, white/stainless								
34000.0065	Ultra-2A, white/stainless, AFI	80.6 kg							
34000.0066	Ultra-2A, black/stainless, AFI								
34000.0071	Ultra-2, white/stainless, painted frame, Spanish	55 kg							
34000.0074	Ultra-2B, black/stainless	62.1 kg	100	12	1200	50/60	I	Yes	   
34000.0084	Ultra-2B, white/stainless								
34000.0091	Ultra-2A, black/stainless		220-230	8.8	1800				
34000.0093	Ultra-2A, white/stainless								
34000.0095	Ultra-2A, white/stainless, coated parts								

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Powdered Ultra[®] Gourmet Ice[®] Systems




- Frozen beverage dispenser with reversing auger technology for superior mixing and freezing*
- Powdered product autofill hoppers refill product at a rate of .03 litre/second.
 - Two large 7.57 litre hoppers for optimum cooling and serving capacity.
 - Reversing auger design quickens freeze time and reduces air mixing.
 - Very simple to program and run with touchpad display, which also guides cleaning and preventive maintenance.
 - Internally monitored refrigeration system ensure long lasting performance.
 - High efficiency LED lighting systems for merchant graphics.
 - Alphanumeric display communicates advertising messages, machine status and technical support contact information in English, Spanish and French. Display capable of showing English or Metric measurements.

RELATED PRODUCTS

Inlet Hose Assembly
 Product No.: 32865.0001

Ultra-2 PAF



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
34000.0502	Ultra-2 PAFA, white/stainless	80.6 kg	220-230	8.8	1800	50/60	I	Yes	CE
34000.0503	Ultra-2 PAFA, all black								
34000.0507	Ultra-2 PAFA, delay refill								

Plumbing: 138-621 kPa. Machine supplied with 1/4" male fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Precise Temperature Water Dispensers



HW2

- Dispenses up to 30.7 litres of hot water per hour
- Space-saving machine just 18cm wide to fit any counter.
- High quality, easy-to-clean stainless steel exterior and tank for a long life.
- Includes drip tray.
- Temperature setting at 93.3°C.
- Perfect for food prep and cleaning.

RELATED PRODUCTS


ED-17-TL
Product No.: 30201.1001





EQ-17-TL
Product No.: 30200.1000

Inlet Hose Assembly
Product No.: 32865.0001

Power Cord
Product No.: 01716.0000



NOTE: Catalog icon legend can be found on page 1.

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
02500.0002	HW2A	10 kg	230	7.6	1750	50/60	1	No	 KSA
02500.0006	HW2A			13.1	3000				
02500.0008	HW2A, 220V, Korea		230	7.6	1750				 CE

Plumbing: 138-621 kPa. Machine supplied with 1/4 inch OD male flare fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Precise Temperature Water Dispensers



H5E PC

- Dispenses up to 68.14 litres of boiling water (H5X) per hour.
- Precise temperature ensures consistent results.
- High quality, easy-to-clean stainless steel exterior and tank for a long life.
- Can be front or side wall mounted for space savings.
- Perfect for preparing large amounts of mashed potatoes, gravy, cheese sauce, gelatin, oatmeal and many more foods.

H5E PC PORTION CONTROL

- Precise electronic temperature control 18.3°C - 96.1°C ensures consistent water temperature.
- Three programmable volume settings and one push and hold continuous dispense button.
- Front of machine volume programming.

RELATED PRODUCTS

EQHP-10
Product No.: 39000.0004

EQHP-10L
Product No.: 39000.0001


Inlet Hose Assembly
Product No.: 32865.0001

Drip Tray
Product No.: 02497.0000

Wall Mount Bracket (side)
Product No.: 12542.0000

Wall Mount Bracket (front)
Product No.: 13125.0001

Shelf Kit
Product No.: 12599.0000







H5E PC



H5E



H5X

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
12500.0056	H5MA, 95.6°C (204°F)	14.5 kg	230	16	3700	50/60	1	No	 KSA
12500.0062	H5EA-40-230, 93.3°C (200°F)								
12500.0063	H5EA-40-230, 29°/46°C (84°/115°F)								
12500.0064	H5XA-40-230, 100°C (212°F)								  KSA
12500.0067	H5EA-40-230, 90°C (194°F)								
39100.0003	H5EA, portion control, 18.3°C - 96.1°C (64.9°F - 205°F)		230	16	3700	50/60			 KSA

Plumbing: 138-621 kPa. Machine supplied with 1/4 inch OD male flare fitting. All plumbed models that are CE listed feature backflow prevention.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Precise Temperature Water Dispensers



H10X

- Dispenses up to 90.85 litres of boiling water per hour.
- Precise temperature 100°C ensures consistent, high quality results.
- Ideal for preparation of large amounts of mashed potatoes, gravy, cheese sauce, gelation, oatmeal, and many more foods.
- Includes dry-plug prevention for easy installation.

RELATED PRODUCTS


EQHP-10
Product No.: 39000.0004



EQHP-10L
Product No.: 39000.0001

Inlet Hose Assembly
Product No.: 32865.0001

Drip Tray
Product No.: 02497.0000



Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
26300.0000	H10X-80-240, 100°C (212°F)	30.26 kg	240	33.5	8050	50/60	I	No	NSF UL LISTED

Plumbing: 138-621 kPa. Machine supplied with 1/4 inch OD male flare fitting.

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Water Quality Filter Systems

Quality beverages begin with quality water

BUNN® water quality filtration systems, when used with BUNN brewing equipment, ensure that your customers are getting the best tasting beverage possible. The Easy Clear® filters are manufactured to BUNN specifications and address water problems such as taste and odor; sediment, limescale and hardness.



Model #	Part #	Capacity @ Flow Rate	Taste & Odor	Sediment	Lime	Softwater	Replacement Cartridges
EQ-17-TL	30200.1000	5678 gal @ 1.9 gpm	•		•		30200.1001
EQHP10L	39000.0001	10000 gal @ 1.5 gpm	•	•	•		39000.1001
EQHP10	39000.0004	10000 gal @ 1.5 gpm	•	•			39000.1004
EQHP25L	39000.0002	25,000 gal @ 2.1 gpm	•	•	•		39000.1002
EQHP25	39000.0005	25,000 gal @ 2.1 gpm	•	•			39000.1005
EQHP35L	39000.0011	35,000 gal @ 3.34 gpm	•	•	•		39000.1011
EQHP54L	39000.0003	54,000 gal @ 5 gpm	•	•	•		39000.1003
EQHP54	39000.0006	54,000 gal @ 5 gpm	•	•			39000.1006
EQHP-TWIN 70L*	39000.0012	70,000 gal @ 6.68 gpm	•	•	•		(2) 39000.1011
EQHP-TWIN 108SP**	39000.0013	108,000 gal @ 10 gpm	•	•	•		(2) 39000.1006, (1) 39000.1010
Scale-Pro®	39000.0010	Recommended 6 month change-out			•		39000.1010
EQHP-ESP	39000.0008	422 gal @ 10.5 gpg @ 5gpm	•				39000.1008
EQHP-SFTN	39000.0009	1350 grains	•			•	39000.1009
EQHP-TEA	39000.0007	4350 grains	•				39000.1007

*Requires two (2) cartridges. **Requires two (3) cartridges

Cleaners

Cleaning Product	Product #	Description	For use with
Coffee Wipes	38450.0000	Coffee Wipe single pack	coffee satin remover
Kay-5®	24634.0001	Box of 50 individual packs	coffee brewers, servers, juice and granita dispensers
	24634.0000	Box of 200 individual packs	
Dezcal™	37306.0000	Cleaning powder (individual pack)	coffee brewers and servers
TABZ™	39637.0000	Cleaning tablets (individual pack)	
	39637.0001	Cleaning tablets (case of twelve)	
GRINDZ™	39159.0000	Grinder cleaner (individual pack)	grinders
	39159.0001	Grinder cleaner (case of twelve)	
Cafiza™	36000.1189	Cleaning tablets (individual pack)	espresso system
	36000.1188	Cleaning tablets (case of twelve)	
Rinza™	39265.0000	Milk froth cleaner (individual pack)	
	39265.0001	Milk froth cleaner (case of six)	
Complete Café™	39265.0010	Espresso machine sanitizer (individual pack)	
	39265.0010	Espresso machine sanitizer (case of six)	

Accessories

Product	Product #	Capacity @ Flow Rate
FLOWJET® System	29875.0001	1.0 GPM (3.8 LPM) at open flow
Frothaway	24700.0000	

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Paper Filters



RESPECT



EARTH®

Selection of coffee filters is a vital step in brewing perfect coffee - don't settle for anything less than BUNN® quality coffee filters. Using the results of years of research, BUNN manufactures the best filters from high quality, heavy weight paper, so the water flows properly through the coffee. BUNN filters are uniquely designed for strength so the sides are taller, and you don't end up with overflow and grounds in your coffee.

BUNN's paper stock used in the manufacturing of our coffee filters is produced using an elemental chlorine-free (ECF) bleaching method.

NOTE: Catalog icon legend can be found on page I.

Filter Type	Product Number	Description	Number per Bag	Bags per Case	Number Cluster	Overall Measure x Base Diameter (millimetres)	Packed per Case	Case Weight (lbs/kg)
Decanter Filters	20115.0000	Regular C, S, R, O, VLPF, VPR, VPS, VP-17	500	2	50	247.65 x 107.95	1000	4.2/1.91
	20116.0000	Regular Narrow C, S, R, O, VLPF, VPR, VPS, VP-17	500	2	50	241.3 x 82.55	1000	4.2/1.91
	20122.0000	Regular Fast Flow C, S, R, O, VLPF, VPR, VPS, VP-17	500	2	50	247.65 x 107.95	1000	4.5/2.04
Urn Filters	20109.0000	Urn - U3, SRU, IC-3	252	1	36	450.85 x 184.15	252	5.5/2.49
	20112.0000	Narrow Base Urn	250	1	25	469.9 x 158.75	250	5.5/2.49
	20124.0000	Urn, 11.4 litres	252	1	36	482.6 x 184.15	252	6.1/2.77
	17104.0001	Urn, 11.4 litres	250	1	25	457.2 x 228.6	250	5.5/2.49
	20111.0000	Titan/Urn, 22.7 litres	252	1	36	508 x 196.85	252	6.6/2.99
	20125.0000	Urn, 22.7 litres	250	1	25	533.4 x 222.25	250	7.5/3.4
	17117.0001	Urn, 22.7 litres	250	1	25	533.4 x 279.4	250	7.5/3.4
	20113.0000	Urn, 37.9 litres	250	1	25	603.25 x 222.25	250	9.3/4.22
Other Filters	20131.0000	Urn, 37.9 litres	252	1	36	615.95 x 273.05	252	9.7/4.40
	20120.0000	System III	252	2	36	384.18 x 136.53	504	8.5/3.86
Gourmet Filters	20100.0000	Tea - Tea Brewers, Single & Dual Coffee brewers, 5.7L urns, ITCB	500	1	50	323.85 x 133.35	500	4.7/2.13
	20100.0010	Gourmet Funnels	500	2	50	323.9 x 133.4	1,000	4.7/2.13
	20138.0000	Gourmet - Iced Tea, system II, Dual, Dual SH, Dual TF, 5.7L urns	252	2	36	349.25 x 133.35	504	5.5/2.49
	20157.0000	BUNN Gourmet C Funnel	500	2	50	349 x 133	1,000	11/4.99

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Coffee Decanters



Easy Pour®
(regular)



Easy Pour®
(decaf)

Easy Pour® is an exclusive BUNN design that assures convenient serving with a drip-proof, fast pouring lip from front or either side

- Glass and Easy Pour® decanters can be private labeled. Please contact your BUNN sales representative for more information.
- All decanters have 1.9L capacity.

Easy Pour®

- Container and handle core are molded as sturdy, extra-strength, one-piece construction for longest life.
- Clear, high-impact-resistant material
- Base is high quality stainless steel.
- Drip-proof, fast-pour lip – an exclusive BUNN design to assure convenient serving. Fast, clean pouring from front or either side.



Glass Decanter
(regular)



Glass Decanter
(decaf)



Stainless Steel Decanter



(decaf)

68

Model	Product #	Number in Case	Handle	Weight
Easy Pour 1.89 litre	06100.0101	1	Black	1.0 lb. (0.5 kg)
	06100.0102	2		2.0 lbs. (0.9 kg)
	06100.0103	3		3.0 lbs. (1.4 kg)
	06100.0106	6		6.0 lbs. (2.7 kg)
	06100.0112	12		12.0 lbs. (5.5 kg)
	06100.0124	24		23.0 lbs. (10.4 kg)
	06100.0156	6 ea. Case of 1		8.0 lbs. (3.6 kg)
	06101.0101	1	Orange	1.0 lb. (0.5 kg)
	06101.0102	2		2.0 lbs. (0.9 kg)
	06101.0103	3		3.0 lbs. (1.4 kg)
	06101.0106	6		6.0 lbs. (2.7 kg)
	06101.0112	12		12.0 lbs. (5.5 kg)
	06101.0124	24		22.5 lbs. (10.2 kg)
Glass Decanter 1.89 litre	06078.0001	1	Black	1.0 lb. (0.5 kg)
	06078.0002	2		2.5 lbs. (1.1 kg)
	06078.0003	3		4.5 lbs. (2.1 kg)
	06078.0006	6		7.5 lbs. (3.4 kg)
	06078.0012	12		15.0 lbs. (6.8 kg)
	06078.0024	24		26.0 lbs. (11.8 kg)
	06089.0017	12		15 lbs. (6.8 kg)
	06089.0018	12	Orange	1.0 lb. (0.5 kg)
	06088.0001	1		2.5 lbs. (1.1 kg)
	06088.0002	2		4.5 lbs. (2.1 kg)
	06088.0003	3		7.5 lbs. (3.4 kg)
	06088.0006	6		14.0 lbs. (6.4 kg)
	06088.0012	12		26.0 lbs. (11.8 kg)
	06088.0024	24		
Stainless Decanter 1.89 litre	06026.0000	1	Black	1.5 lbs. (0.7 kg)
	06041.0000		Orange	

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Coffee Decanter Warmers



WS2B

- Warmers are an ideal way to merchandise the aroma and appearance of your fresh-brewed coffee in decanters at remote serving stations.
- Each warmer has a separate “on/off” switch and maintains coffee at optimum serving temperature.



RELATED PRODUCTS

Power Cord
Product No.: 01716.0000






WX2


RELATED PRODUCTS



WS2B



WX2



WX2A

Product #	Description	Weight	Volts	Amps	Watts	Hertz	Phase	Cord	Agency
12882.0002	WS2B, 2 position warmer	3.2 kg	100	2	200	50	I	Yes	
06310.0006	WX2A, 2 position warmer	1.8 kg	230	I	200	50/60	I	No	

Airpot Racks



UNIV-4 APR

- Holds either push-button or lever-action airpots.
- Designed to display 2, 3, 4, 5 or 6 airpots.
- Sturdy, carbon-steel wire construction with vinyl coating resists corrosion and is easy to clean.
- Sponge-lined trays to catch drips and spills.

** For detailed drawings, please refer to on-line spec sheets at www.bunn.com*

70



UNIV-2 APR



UNIV-2 APR
(2 lower)



UNIV-3 APR



UNIV-6 APR

Product #	Description	Weight	Capacity	Dimensions	Agency
35728.0000	UNIV-2 APR, 1 upper, 1 lower	2.3 kg	2 airpots	35.8 H x 19.1 W x 61.2 D	
35728.0001	UNIV-2 APR, 2 lower	2.0 kg	2 airpots	17.5 H x 37.9 W x 28.5 D	
35728.0002	UNIV-3 APR, 3 lower	2.7 kg	3 airpots	17.5 H x 58.2 W x 28.5 D	
35728.0003	UNIV-4 APR, 2 upper, 2 lower	4.5 kg	4 airpots	35.6 H x 37.9 W x 63.3 D	
35728.0004	UNIV-5 APR, 3 upper, 2 lower	5.9 kg	5 airpots	35.6 H x 58.2 W x 63.3 D	
35728.0005	UNIV-6 APR, 3 upper, 3 lower	6.8 kg	6 airpots	35.6 H x 58.2 W x 63.3 D	

Dimensions shown in centimetres For capacities, additional specs, manuals, care & cleaning, visit www.bunn.com.

Stock Funnels



BLACK PLASTIC SPLASHGARD® FUNNEL WITH DECALS

Product #: 20583.0003

- For use with CDBC, CWT, AXIOM® and SmartWAVE® brewers.



BLACK PLASTIC ITCB FUNNEL

Product #: 03021.0008

- For use with ITCB when brewing coffee.



BLACK PLASTIC SINGLE/DUAL FUNNEL

Product #: 22735.0000

- For use with Single®, Dual® and Soft Heat® brewers.



STAINLESS STEEL SPLASHGARD® FUNNEL

Product #: 20216.0000

- For use with CDBC, CWT AXIOM® and SmartWAVE® brewers.



STAINLESS STEEL DUAL/SINGLE FUNNEL

Product #: 20201.1201

- For use with Single®, Dual®, and Soft Heat® brewers.



SMART FUNNEL®

Product #: 32643.0000

- For use with BrewWISE® ThermoFresh®, Soft Heat®, DBC® and ICB brewers.



TITAN™ FUNNEL

Product #: 40114.0000

- For use with Titan™ brewers



URN FUNNEL

Product #: 07022.0012

- For use with SRU and U3 brewers



TRANSLUCENT TEA FUNNEL

Product #: 03021.0004 (standard)

- For use with ITCB, TB3 and TU3 brewers

Product #: 03021.0005 (quick dispense)

- For use with ITB, TB3Q and TU3Q brewers

NOTE: All funnels shown are designed with SplashGard® to help deflect hot liquids away from the hand.

Special Purpose Funnels



TRANSLUCENT TEA FUNNEL

Product #: 03021.0005

- For use with (quick dispense) TU3Q.

Product #: 03021.0005

- For use with TU3, TB3, and ITCB.
- SplashGard® deflects hot liquids away from the hand when removed.



TRANSLUCENT POUCH PACK FUNNEL

Product #: 20583.0003

- For use with TU3, TU3Q, TB3, and ITCB.
- Use with rectangular tea pouch pack.
- See through material guards against hot water spills when removed.



UNIVERSAL STAINLESS POUCH PACK FUNNEL

Product #: 29151.0000 (black handle)

Product #: 29151.0001 (orange handle)

- Interchangeable handle allows use in all BUNN decanter brewers.



POUCH PACK FUNNEL FOR SATELLITE BREWERS

Product #: 35282.0000 (black)

- For Duals and Singles.



POUCH PACK FUNNEL - SMALL BREW CHAMBER

Product #: 02074.0010 (black)

- For use with F, O, R & X brewers.

Product #: 04274.0012 (black)

Product #: 04274.0010 (brown)

- For use with S, VP, & CWTF brewers.



POUCH PACK FUNNEL - LARGE BREW CHAMBER

Product #: 02074.0010 (black)

- For use with F, O, R & X brewers.

Product #: 02774.0011 (black)

Product #: 02774.0010 (brown)

- For use with S, VP, & CWTF brewers.



GOURMET C FUNNEL

Product #: 34559.0000

- For use with CDBC, CWT AXIOM® and SmartWAVE® brewers
- Universal design – handle may be moved to appropriate side
- Allows brewing with heavier throw weights of coffee.



TRANSLUCENT COFFEE FUNNEL

Product #: 20583.0002 (standard)

- For use with S, VP, and CWTF brewers

Product #: 29351.0000 (wide)

- For use with F, O, R, and X brewers

Drip Trays

COFFEE EQUIPMENT



SINGLE®, SINGLE SH BREWERS AND SINGLE SH STAND

Product #: 26830.0000 Kit
Product #: 26918.1000 Drip Tray
Product #: 26801.0000 Drip Tray
Cover




AIRPOT RACK

Product #: 25368.0000 Drip Tray
Product #: 25367.0000 Drip Tray
Sponge Liner



RWSI WARMER

Product #: 20213.0103 Kit
Product #: 20213.0301 Bracket
Product #: 20213.0200 Drip Tray
Product #: 03229.0000 Drip Tray
Cover



HW2, H5M, H5E, AND H5X

Product #: 02497.0000 Kit
Product #: 02545.0000 Drip Tray
Only
Product #: 02546.0000 Drip Tray
Cover
Product #: 02547.0000 Foot,
Rubber (Not pictured. Four (4) are
required.)



DUAL®, DUAL SH BREWERS AND 2SH STAND

Product #: 27150.0000 Kit
Product #: 26971.1000 Drip Tray
Product #: 26916.0000 Drip Tray
Cover



DUAL® BREWERS

Product #: 20213.0101 Kit
• Includes Drip Tray, Drip Tray Cover,
and Bracket.



NEW THERMOFRESH® SERVER

(for servers shown on pages 28-29)
Product #: 38931.1002 Kit
• Includes Drip Tray and Drip Tray
Cover.



SRU COFFEE URN

Product #: 06465.0000 Kit
• Includes everything shown.



U3 COFFEE URN

Product #: 07284.0000 Kit
Product #: 07286.0000 Drip Tray
Product #: 07285.0000 Drip Tray
Cover

Drip Trays

TEA DISPENSERS



TCD AND TDO


Product #: 38029.1000 Kit
Product #: 26801.0004 Drip Tray
Product #: 26801.0000 Drip Tray Cover

FRESH MIX DISPENSERS




FMD-1 AND FMD-2

Product #: 02571.0000 Drip Tray
Product #: 28966.0000 Drip Tray Cover



FMD-3

Product #: 28699.0000 Drip Tray
Product #: 28267.0000 Drip Tray Cover



FMD-4 AND FMD-5

Product #: 34716.0000 Drip Tray
Product #: 34717.0000 Drip Tray Cover



iMIX-3

Product #: 36984.0000 Drip Tray
Product #: 36985.0000 Drip Tray Cover



iMIX-4 AND iMIX-5

Product #: 36670.0000 Drip Tray
Product #: 36739.0000 Drip Tray Cover

GOURMET JUICE® SYSTEMS




JDF-2 S

Product #: 38765.0000 Kit
Product #: 38765.1000 Drip Tray
Product #: 26801.0000 Drip Tray Cover




JDF-2 S EXTENDED

Product #: 44015.1000 Kit
Product #: 26801.0000 Drip Tray Cover
• Increases cup clearance to 10.25"



JDF-4 S

Product #: 38764.1001 Kit



JDF-4 S EXTENDED

Product #: 40789.1000 Kit
Product #: 33811.0000 Drip Tray Cover
• Increases cup clearance to 10.25"

GOURMET ICE® SYSTEMS



ULTRA-2 WHITE

Product #: 28086.0000 Drip Tray
Product #: 32068.0000 Drip Tray Cover



ULTRA-2 BLACK

Product #: 28086.0001 Drip Tray
Product #: 32068.0001 Drip Tray Cover

International and US Government Contacts

Sales/Service/Support

CORPORATE OFFICES

1400 Stevenson Drive
Springfield, Illinois 62703 USA
(800) 637-8606 or (+1) 217-529-6601

INTERNATIONAL OFFICE

1400 Stevenson Drive
Springfield, Illinois 62703 USA
(+1) 217-529-6601
Fax: (+1) 217-529-2827
international@bunn.com

WESTERN REGIONAL OFFICE

16431 Carmenita Road
Cerritos, California 90701 USA

CANADA OFFICE

280 Industrial Parkway
South Aurora, Ontario, L4G 3T9 Canada
(+1) 905-841-2866

MEXICO OFFICE

Aniceto Ortega #817
Col. Del Valle, Del. Benito Juarez
CP 03100 Mexico, D.F.
(+52) (555) 575-7961
Fax: (+52) (555) 559-1608

UNITED KINGDOM OFFICE

7 Beaufort Court,
Roebuck Way, Knowlhill
Milton Keynes, MK5 8HL
United Kingdom
(+44) 1908 241 222
Fax: (+44) 1908 241 224

GERMANY OFFICE

Paul-Gerhardt-Allee 49/1
81245 München Germany
(+49) 89-896-09950
Fax: (+49) 89-896-09999

REPRESENTATIVE OFFICE

China

DISTRIBUTION FACILITIES

Springfield, Illinois USA
Moonachie, New Jersey USA
Cerritos, California USA
Manchester, United Kingdom
Mexico City, Mexico

USA Technical Service Department

(+1) 217-585-5903
Fax: (+1) 217-529-2177
tech.service@bunn.com

EMEA Technical Service Department

(+44) 1908 241 222
Fax: (+44) 1908 241 224
emea.warranty@bunn.com

INTERNATIONAL SALES

Brian Wisniewski, Sr.VP & GM
International Sales
(+1) 217-585-3238 office
Fax: (+1) 312-296-8277
brian.wisniewski@bunn.com

Sam Grasinger, VP International Sales
Latin America, Caribbean
(+1) 217-585-4553 voice mail
Fax: (+1) 217-585-4965
sam.grasinger@bunn.com

Avi Sandler, Sales Director
Mexico
(+52) (555) 575-7961 office
Fax: (+1) 217-585-5959
avi.sandler@bunn.com

Victor Rodriguez, Sales Director
Andean, Caribbean
(+1) 305-588-0350 cell
(+1) 217-585-4554 voice mail
Fax: (+1) 217-585-5958
victorrodriquez@bunn.com

Luiz Salomão, Commercial Representative
South America Southern Cone
(+55) 11-9452-4312 cell
Fax: (+1) 217-585-3049
luiz.salomao@bunn.com

Lina Chiodo, VP of Sales & Marketing
Europe, Middle East, Africa
(+1) 416-233-1200 office
(+44) 1908 241 222 UK office
(+1) 647-998-4809 cell
Fax (+1) 217-585-7390
lina.chiodo@bunn.com

Giulia Spanio, Area Manager
Europe
(+39) 3316746274 cell
Fax: (+1) 217-585-5958
giulia.spanio@bunn.com

David Locker, Sales Manager
UK, Ireland
(+44) 1908 241 222 UK office
(+44) 7787 510 062 cell
Fax: (+1) 217-585-4592
david.locker@bunn.com

Peter Muschiol, Sales Coordinator
Germany and Eastern Europe
(+49) 17 289 00526 cell
Fax: (+1) 217-585-3043
peter.muschiol@bunn.com

Billy Chang, VP Service and Marketing
Asia, Pacific
(+1) 217-306-3554 cell
(+1) 562-926-0764 office
Fax: (+1) 217-585-4958
billy.chang@bunn.com

SALES (continued)

CheeWu Ho, VP Sales and Marketing
Asia, Pacific
(+65) 67954871 cell
Fax: (+1) 217-585-5958
cheewu.ho@bunn.com

CC Tan, Director of Sales
Asia Pacific, Sub Continent
(+65) 9237-0189 cell
Fax: (+1) 217-585-3050
cc.tan@bunn.com

Lisa Burchfield, Manager International and
US Government Sales
(+1) 217-306-3546 cell
Fax: (+1) 217-585-5968
lisa.burchfield@bunn.com

TECHNICAL

Dago Castro, Service Director
Latin America, Caribbean
(+1) 305-439-9462 cell
(+1) 217-585-4555 voice mail
Fax: (+1) 217-585-4957
dago.castro@bunn.com

Ventura Ordonez, Director of Tech Support
Mexico
(+52) (555) 575-7961 office
Fax: (+52) (555) 559-1608
ventura.ordonez@bunn.com

Mike Khan, Technical Manager
Europe, Middle East, Africa
(+44) 1908 241 222 UK office
(+44) 7966 067 172 cell
Fax: (+1) 217-585-3041
mike.khan@bunn.com

Keith Collins, Director of Services
Europe, Middle East, Africa
(+44) 1908 241 222 UK office
(+44) 7792 052 386 cell
Fax: +1 217-585-7052
keith.collins@bunn.com

Walter Sun, Technical Manager
Asia Pacific
(+86) 13916606037 cell
waltersun@bunn.com


Adre Silva, Technical Representative
South America
(+55) 97303876 cell
andre.silva@bunn.com

BUNN®

Bunn-O-Matic Corporation

1400 Stevenson Drive • Springfield, IL 62703, USA

Phone: +1 (217) 529-6601 • Fax: +1 (217) 529-2827

www.bunn.com 

E9000.0047F 2/11 © 2004 Bunn-O-Matic Corporation



Our continuing focus on preserving
the earth for future generations.